

AGENDA ITEM FOR ADMINISTRATIVE MEETING () Discussion only
(X) Action

FROM (DEPT/ DIVISION): County Counsel

SUBJECT: Used Drum Roller Purchase

<p>Background: The County issued a request for proposals for the purchase of a used roller drum for the Public Works Department. Two proposals were received.</p> <p style="padding-left: 40px;">Indian Eyes, LLC - \$73,450 Pape Machinery, Inc. - \$92,500</p> <p>The recommendation is to award the contract to the lower proposal.</p>	<p>Requested Action: Approve contract for the purchase of the used drum roller from Indian Eyes, LLC in the amount of \$73,450</p>
--	--

ATTACHMENTS: Proposals

*****For Internal Use Only*****

Checkoffs:

- () Dept. Heard (copy)
- () Budget (copy)
- () Fiscal
- (X) Legal (copy)
- () (Other - List:)

To be notified of Meeting:
Tom Fellows

Needed at Meeting:

Scheduled for meeting on: February 21, 2024

Action taken:

Follow-up:



Indian Eyes, LLC
5826 W. Van Giesen Street, West Richland, WA. 99353
Phone: 509-542-1114
Fax: 509-542-1793
E-mail: Mac@IndianEyesLLC.com
Web-site: www.IndianEyesLLC.com



Date: February 14, 2024

To: Tom Fellows
Public Works Director
Umatilla County Public Works
3920 Westgate
Pendelton OR 97801

From: Indian Eyes, LLC
5826 W. Van Giesen Street
West Richland, WA. 99353
Phone: 509-542-1114
Fax: 509-542-1793
E-mail Address: mac@IndianEyesLLC.com

Subject: Solicitation No: Single Drum Roller 2024
Offeror Due Date: February 14, 2024; 11:00 PST
DUNS #: 19-089-4845
CAGE Code: 37UF0
Tax ID No: 83-0422887

Indian Eyes, LLC is pleased to submit the following proposal. Indian Eyes agrees to hold the prices in this offer firm for 30 calendar days from the date specified above.

Description of the Organization:

Indian Eyes, LLC is an SBA Certified Small business specializing in Fleet Services/Equipment, Program/Project Management, Staffing and Resource support services. Indian Eyes, LLC is headquartered in West Richland Washington..

Size Standard Certification:

Indian Eyes, LLC is classified as a small business as determined by the Small Business Administration within North American Classification System (NAICS) Code 532412 size standards.

Offer Representations and Certifications

The offeror has completed the annual representations and certifications electronically via the SAM website at www.sam.gov. After reviewing the SAM database information, the offeror verifies by submission of this offer that the representations and certifications currently posted electronically at FAR 52.212-3, Offeror Representations and Certifications--Commercial Items, have been entered or updated in the last 12 months, are current, accurate, complete, and applicable to this solicitation (including the business size standard applicable to the NAICS code referenced for this solicitation), as of the date of this offer and are incorporated in this offer by reference.

Single Drum Roller
Indian Eyes, LLC



Contact Information:

Following is the contact information for the primary individual responsible for the management of the proposed contract;

Primary Contact:

Name: Mac McCullough
Phone: 509-542-1114
Fax: 509-542-1793
Cell: 509-380-6261
E-mail: mac@IndianEyesLLC.com
Address: 5826 W. Van Giesen St.
West Richland, WA. 99353

Offer 1	Item Description	Unit Price
0001	1) 2016 BOMAG 211 D-50 S/N 101585401312 *84" Single Smooth Drum vibratory roller includes cab and HVAC (Heat and Air), tires at 50% or better and ready to work. Hours approximately 2,575. Includes Delivery to Pendleton Area	\$ 73,450.00

Delivery

- Indian Eyes shall deliver the equipment to Umatilla County Public Works in the Pendleton Area.
- As part of planning operations, an Indian Eyes representative will coordinate with the POC prior to delivery.

Invoicing

Indian Eyes standard commercial invoices shall be utilized as the primary invoicing document to effect payment.

Payment of Invoices

Payment Terms; Net 30 days from receipt of invoice.

If you have any questions or require additional information. Please contact us at 509-380-6261, e-mail: Mac@IndianEyesLLC.com,

Respectfully,

Shane "Mac" McCullough
VP Operations
Indian Eyes, LLC

Single Drum Roller
Indian Eyes, LLC

Quote Id: 30337274

Prepared For:
UMATILLA COUNTY PUBLIC WORKS

Prepared By: **RALPH GOODWIN**

Pape Machinery, Inc.
1925 E James Street
Pasco, WA 99301

Tel: 509-547-8813

Mobile Phone: 509-995-4706

Fax: 509-547-7959

Email: rgoodwin@papemachinery.com

Date: 07 February 2024

Offer Expires: 08 March 2024

Quote Summary

Prepared For:
 UMATILLA COUNTY PUBLIC WORKS
 3920 WESTGATE
 PENDLETON, OR 97801
 Business: 541-278-5424

Prepared By:
 RALPH GOODWIN
 Pape Machinery, Inc.
 1925 E James Street
 Pasco, WA 99301
 Phone: 509-547-8813
 Mobile: 509-995-4706
 rgoodwin@papemachinery.com

This sale is subject to Papé's Terms and Conditions of Sale effective on the date hereof, which are incorporated in full by this reference. The Terms and Conditions of Sale are available at www.pape.com/terms, and will also be sent by mail or e-mail to the purchaser upon request.

Quote Id: 30337274
Created On: 07 February 2024
Last Modified On: 09 February 2024
Expiration Date: 08 March 2024

Equipment Summary	Selling Price	Qty	Extended
2021 HAMM H10i SOIL COMPACTOR, 12T, 84"DRUM - H2352041	\$ 92,500.00	X 1 =	\$ 92,500.00

Equipment Total **\$ 92,500.00**

Quote Summary

Equipment Total	\$ 92,500.00
SubTotal	\$ 92,500.00
Total	\$ 92,500.00
Down Payment	(0.00)
Rental Applied	(0.00)
Balance Due	\$ 92,500.00

Salesperson : X _____

Accepted By : X _____

Selling Equipment


MACHINERY
Quote Id: 30337274

Customer: UMATILLA COUNTY PUBLIC WORKS

2021 HAMM H10i SOIL COMPACTOR, 12T, 84"DRUM - H2352041

Hours: 806

Stock Number: H2352041

Code	Description	Qty
H 10i	HAMM SOIL,12T,84"DRUM	1
Standard Options - Per Unit		
-	MULTI-PURPOSE TIRES	1
-	WARNING LABELS ACCORDING TO ANSI	1
-	PLASTIC SCRAPER FOR SMOOTH DRUM	1
-	ROPS RIGID	1
-	DRIVER SEAT BLACK IMITATION LEATHER	1
-	STEERING COLUMN WITH TILTABLE DASHBOARD	1
-	ROTATING SEAT ADAPTER	1
-	LIGHTING PACKAGE	1
-	BACK-UP ALARM W/VOL ADJUSTMENT	1
-	LUNCH BOX HOLDER	1
-	84" DRUM WIDTH, 1" DRUM THICKNESS, DRUM DRIVE	1
ENGINE S/N	12531871	1
S/N	H235.2041	1

H 10i

Compactor with smooth drum

Compactors Series H / Series H235




HIGHLIGHTS H

- > 3-point articulation for excellent traction and cross-country mobility
- > Operating concept Easy Drive
- > Electronic machine management Hammtronic
- > Excellent view of machine and construction site
- > High compaction performance due to linear load and big amplitudes

Machine dimensions

Total length (L)	mm • in	230.3 • 230.3
Width (B)	mm • in	89.9 • 89.9
Total height (H)	mm • in	116.5 • 116.5
Drum width (X)	mm • in	84.3 • 84.3
Height, loading, min. (HI)	mm • in	90.9 • 90.9



EU Stage
IV/EPA Tier
4

TECHNICAL DATA		Unit	H 10i
Weights			
Operating weight with cab	kg • lbs	10880 • 23,990	
Operating weight with ROPS	kg • lbs	10630 • 23,439	
Operating weight, max.	kg • lbs	13290 • 29,304	
Axle load, front/rear	kg • lbs	5890/4990 • 12,987/11,003	
Static linear load, front	kg/cm • lbs/in	27,5 • 154,0	
Machine dimensions			
Total length	mm • in	5850 • 230,3	
Total height with cab	mm • in	2960 • 116,5	
Height, loading, min.	mm • in	2308 • 90,9	
Wheelbase	mm • in	3150 • 124,0	
Total width with cab	mm • in	2284 • 89,9	
Ground clearance, center	mm • in	390 • 15,4	
Turning radius, inside	mm • in	3870 • 152,4	
Angle of driving slope, front/rear		53/32	
Drum dimensions			
Drum width, front	mm • in	2140 • 84,3	
Drum diameter, front	mm • in	1504 • 59,2	
Drum thickness, front	mm • in	25 • 1,0	
Drum type, front		Smooth	
Wheel dimensions			
Size of tires, rear		AW 23.1-26 12 PR	
Diesel engine			
Manufacturer		DEUTZ	
Type		TCD 3.6 L4	
Number of cylinders		4	
Power rat. ISO 14396, kW/PS/rpm		85,0/115,6/2300	
Power rating SAE J1349, kW/HP/rpm		85,0/113,9/2300	
Emission standard		EU Stage IV/EPA Tier 4	
Exhaust gas after-treatment		DOC-SCR	
Drive			
Speed, infinitely variable	km/h • mph	0-12,0 • 0,0-7,5	
Regulation, infinitely variable		Hammtronic	
Climbing ability, vibration on/off		54/59	
Vibration			
Vibration frequency, front, I/II	Hz • vpm	30/36 • 1,800/2,160	
Amplitude, front, I/II	mm • in	2,04/0,84 • 0,80/0,33	
Centrifugal force, front, I/II	kN • lbs	246/136 • 55,350/30,600	
Steering			
Oscillation angle +/-		10	
Steering, type		Articulated steering	
Tank capacity/Fill capacity			
Fuel tank, capacity	L • Gal	280 • 74,0	
AdBlue/DEF tank, content	L • Gal	32 • 8,5	
Sound level			
Acoustic power LW(A), sticker		104	
Acoustic power LW(A), measured		101	

EQUIPMENT

2 large working and rear view mirrors, 2 multiply-adjustable armrests, 3-point articulation, Storage bin, lockable, Dashboard with displays, indicator lights and function key, Automatic traction control and anti-slip control, Operating concept Easy Drive, ECO mode, Speed preselect, Cup holder, Hammtronic—electronic machine management, Hose protection on front vehicle, Vibration-isolated operator's platform, Space for cooler, Stepless hydrostatic all-wheel drive, Automatic vibration system, ROPS, rigid

OPTIONAL EQUIPMENT

HCQ navigator, Rotating seat adapter, Steering column with comfort exit and tiltable dashboard, Combination scraper for smooth drum and padfoot shells, Rotating beacon, Dozer blade, Protective roof, Padfoot shell, Auxiliary heater, Working light, Back-up alarm, Frequency control, Radio, ROPS cabin with heating, FOPS-approved (level I), ROPS cabin with heating and air conditioning, FOPS-approved (level I), Safety belt monitoring device, Automatic engine-off function, Engine hood with electrical easy access engine cover release, Telematics interface, WIFMS fleet management interface

WIRTGEN AMERICA

6030 Dana Way
 Antioch, TN 37013
 615-501-0600
 Fax 615-501-0691
www.wirtgen-group.com/america

HAMM AG

Hammstraße 1
 D-95643 Tirschenreuth
 Tel. +49 9631 80-0
 Fax +49 9631 80-111
www.hamm.eu

