

AGENDA ITEM FOR ADMINISTRATIVE MEETING () Discussion only
(X) Action

FROM (DEPT/ DIVISION): Public Works
PROGRAM: 45300-602900 Equipment Misc.
SUBJECT: Mobile Emulsion Tank

<p>Background:</p> <p>The Public Works Department is requesting approval to purchase a Cimline T1 mobile emulsion tank. This is to work in line with the Durapatcher that we currently operate. Currently we receive our emulsion for patching in 225 gallon totes; these totes are not heated and they are very messy and inefficient when transferring from tote to machine. We lose a day of patching every time we have to fill the machine due to the need to heat the product. The new emulsion tank is heated, has a pump to transfer the oil machine to machine, holds 1,000 gallons of product and should be much more efficient. The machine delivered to Pendleton will be \$47,584.60. The pricing utilizes a Sourcewell contract.</p>	<p>Requested Action:</p> <p>Authorize purchase of Cimline Mobile Emulsion Tank from MetroQuip Inc. in the amount of \$47,584.60</p>
--	---

ATTACHMENTS: Price Quote from MetroQuip Inc.
Date: (4/28/25) Submitted by: (Tom Fellows)

*****For Internal Use Only*****

Checkoffs:

- () Dept. Heard (copy)
- () Human Resources (copy)
- () Fiscal
- () Legal (copy)
- () (Other - List:)

To be notified of Meeting:

Needed at Meeting:

Scheduled for meeting on: May 7, 2025

Action taken:

Follow-up:



QUOTE

MetroQuip, Inc.

1953 E. Commercial
 Meridian, ID 83642
 ph:(208)344-3318 fax:(208)345-5931

QUOTATION NO. CimlineT1
 DATE April 17, 2025
 CUSTOMER ID UmatillaCounty
 EXPIRATION DATE 30 Days

TO Brian Johnson
 Umatilla County Road Dept
 3920 Westgate Street
 Pendleton, OR 97801
 PH: 509-520-7978

brian.johnson@umatillacounty.gov

SALESPERSON	FOB	PAYMENT TERMS	DUE DATE
Jeff McCoy (208)921-5332	Pendleton, OR	Standard Terms and Conditions	

LEAD TIME - APPROX 60 DAYS ARO

QUANTITY	DESCRIPTION	UNIT PRICE	LINE TOTAL
1.00	Cimline T1 Mobile Emulsion Tank with Durapatcher Technology Emulsion Capacity: 1000 Engine: 5HP Gas Honda Heating Method (overnight): Electric Blanket Heat Rating (watts): 1500 x 2, 110VAC Material Pump: 15 gpm GVWR (lbs):12,500 GAWR (lbs):7000x2 Axles/ Suspension:2 (slipper spring) Brake Type:Electric Loading Hose: 2" ID x 96" Loading Ports: 14" x2 (one vented and lockable) Fuel Capacity: 2 gallons Insulation: 2" with fiber reinforced cover Trailer Construction: 2" x 6" x 1/4" Tube Steel Drain Valve:3" Temperature Gauge: 5" Dial type Dimensions (l x w x h): 190" x 90" x 90" Shipping Weight :3,760 lb.	\$45,084.60	\$45,084.60
	Pricing Utilizing Sourcewell Contract #080521-CMF.		
1.00	Freight - Pearl, MS to Pendleton, OR	\$2,500.00	\$2,500.00

This is a quotation for the goods named, subject to the conditions noted below. This quotation is valid for 30 days from date above unless otherwise noted. The prices do not include freight charges, sales tax, F.E.T., or other applicable taxes unless noted. All sales are subject to availability and/or prior sale.

SUBTOTAL	\$	47,584.60
SALES TAX		
TOTAL	\$	47,584.60

To Accept this quotation, sign here and return: _____

THANK YOU FOR YOUR BUSINESS!

T1

Mobile Emulsion Storage/Delivery Tank



Maximize Your Patching Efficiency:

The Cimline T1 emulsion transport trailer will improve your efficiency by having emulsion on site for your patching crew. When the T1 is paired with a spray injection patcher, your crew stays on the job site longer, saving time and money with fewer trips to the emulsion plant. The T1 further optimizes your operation with the ability to heat emulsion to your climate and application specifications easily and quickly with powerful electric heating blankets.



1,000-gallon Capacity Tank:

Allows crews more time and efficiency on the job site with three to four times the emulsion storage capacity of a standard spray patching unit. A recirculation circuit and 5hp Honda driven 15gpm Viking pump in the plumbing provides agitation keeping the emulsion properly mixed.

Electric Heated Thermostatic Controlled:

Two 1500-watt, 110-volt heating blankets are thermostatically controlled to maintain the optimum emulsion application or storage temperature. Blanket heating also allows the tank to be preheated preventing emulsion shock and helping extend the life of your emulsion.

Fast Filling:

Filling the T1 tank is simple with the large 14" vented, locking loading port. Loading your patcher is fast and easy with a 15gpm pump and 1-1/2" x 10' heavy duty flexible rubber hose with cam lock quick connects.

Heavy Gauge Insulated Tank:

The tank features two-inches of insulation and it is protected from the elements with a fire retardant cover.



Electric Overnight Heating System



Large Temperature Gauge



5 Gallon Solvent Tank For System Flush



5hp Gas Engine & 15gpm Gear Pump



Large 14" Lockable Tank Fill Port



Skid Model Available

SPECIFICATIONS

Cimline T1

#408129

Material Capacity	1000 US Gallons
Engine	5hp Gas Honda
Engine Fuel Capacity	2 US Gallons
Heating Method	Electric Blanket
Heat Rating	1500w x 2, 110VAC (220VAC Optional)
Material Pump	15GPM Viking Gear Pump
Loading Hose	1-1/2" ID x 10' Flexible Heavy Duty Rubber
Material Outlet Port	1-1/2 Inch With Cam Lock Coupling
Loading Ports	14" x 2 (One is Locking and Vented)
Temperature Gauge	5 Inch Analog Dial Type
Drain Valve	3" Brass Ball Valve
Tank Insulation	2" With Fiber Reinforced Protective Cover
Trailer Construction	2"x6"x1/4" Tube Steel
Trailer Braking	Electric
Axles/Suspension	2x7000Lbs./Slipper Spring
Dimensions (LxWxH)	190 x 90 x 90 Inches
GVWR	14,000Lbs.
Shipping Weight	3760Lbs.
Warranty	1 Year

Due to continuous improvement, specifications are subject to change without notice.



Learn more at cimline.com

Phone : 800-328-3874 Email : orders@cimline.com

DURAPATCHER
TECHNOLOGY

© 2021 Cimline Inc. All rights reserved.

PRODUCTS FROM CIMLINE



P2™ Two-Person Patcher
with DuraPatcher™ Technology



P5™ One-Person Patcher
with DuraPatcher™ Technology



T-Series™ Stationary
Emulsion Storage Tanks