

**Request for Proposal  
Blue Mountain Station Steel Bridge**

Umatilla County is requesting proposals for the purchase of a prefabricated modular steel vehicular bridge. The bridge shall have a clear roadway width of 24 feet and a center of bearing to center of bearing span length of 50 feet. Metal decking shall be structural and capable of supporting traffic loading and 6" of asphalt concrete pavement. Decking shall have a minimum thickness of 9-gauge and shall be galvanized. Steel paving dams shall be provided along both edges of the bridge and shall extend at least 6 inches above the metal decking. Bridge railings shall be galvanized thrie beam with appropriate end sections and shall be designed to TL-2 or greater standards. Fabricated steel backwalls for each end of the bridge shall be provided and shall completely cover the end of the bridge girders and extend beyond the sides of the bridge to a minimum of 5 feet. All structural steel with the exception of the metal decking and backwall panel sheeting shall be weathering steel. Bearings and anchor bolts shall be included with the bridge.

The bridge superstructure shall be designed by the manufacturer for a HL-93 live load in accordance with the current AASHTO LRFD bridge design specifications and shall include design drawings stamped and signed by an Oregon Professional Engineer. The proposal shall include design, fabrication, and delivery of all bridge components to the project site at the intersection of Blue Mountain Station Road and Couse Creek Road just South of Milton-Freewater, Oregon in Umatilla County. Both price and delivery date will be taken into account in determining the best option for Umatilla County.

Proposals shall be made lump sum and include all costs to design, fabricate, and deliver the bridge to the site. Unloading of the bridge components at the site will be performed by others.

Proposals shall be submitted by mail or hand delivered to the Umatilla County Public Works Director's office at 3920 Westgate Street, Pendleton, Oregon 97801 no later than 4:00 PM on June 30, 2026. Proposals shall be clearly marked "Blue Mountain Station Steel Bridge Proposal". Further information may be obtained by contacting Tom Fellows at Umatilla County 541 278-5424

Umatilla County may reject any proposal not in compliance with all prescribed public bidding procedures and requirements and reserves the right to reject any or all proposals and to accept the proposal deemed to be in the public interest.