

Field notes of the Town of Sommerville  
as laid out at request of S L Morse

Feb'y 7 & 8. 1882

Set post as initial point fifty feet from the center of the  
R R grade on the line between the S & SW 1/4 of the NW 1/4 of Sec 10  
T 2 N R 32 E. From which point I run north on said line a distance  
of 300 feet driving post at each 100 feet. From the terminus of the  
300 feet I continued north 60 feet and set post. I then continued  
said sixty feet at right angles with said line a distance of 1000 feet  
marking streets & blocks on either side as hereinafter shown. A  
strip of sixty feet running E & W I designated Main Street and from  
it all other streets together with all blocks are laid off at right  
angles. said streets and blocks run from said main street  
to the Umatilla river and south from said street to a line drawn  
parallel to the line of the R R and fifty feet north of the center  
of said R R grade. Main Street is sixty feet wide and all  
others 30 feet. Lots are 100x100. Blocks & lots started off  
lettered & numbered as shown in plat. Said town is situated  
within the S E 1/4 of the NW 1/4 of Sec 10 T 2 N R 32 E of Umatilla County  
Oregon.

I hereby certify that the above is a true description  
of the town of Sommerville as laid out by me. Feb'y 6 & 7 1882

Dated Feb'y 9<sup>th</sup> 1882

J. N. Raley  
Co. Surveyor

Filed Feb'y 9<sup>th</sup> 1882 at 10 o'clock am  
J. R. Kenney clk