



Fnd 1/2" IP in  $\square$  of Road  
 as projected from south +  
 in line with old E-W Fence Line  
 Pipe is 7.3' East + 1.4' N. of BC. by  
 Harris I.P. with Flared bottom.  
 Pipe badly Corroded. added 1 IP.  
 Through Center To Preserve Remains  
 for Record.  
 It should be noted that Kimbrell Records the  
 6/7 section line as 5318.5.  
 Kim. error index = 5316.1  
 Edwards survey = 5316.0  
 Original = 5314.6

Set 7/8" IR  
 10.2' west (on line from East)  
 of present 5/8" IR on East  
 edge of Pavement. (Use 5/8" IR  
 as wit. corner)

Fnd 1/4" IP (Kimb 1910)  
 2' UG  $\perp$  under 4" I. Post. set  
 by John Walchli many years  
 ago to Preserve location of  
 this 1910 IP.

Corner set by U.S. Fish &  
 Wildlife 1934 (BC) at approx.  
 $\square$  of Roads N-S + EW. 30' N +  
 30' W. of then Existing  
 Fence corner. Corner  
 obliterated and present 1/4"  
 IP set by U.S.F.W. 1958 using  
 same data. Refer Robert  
 Ducret - Chief Surveyor U.S.F.W.

NOTES

(\*) Kimbrell's Distances of Record

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

W. W. Gramer

OREGON  
SEPT. 30, 1977  
WALTER W. GRAMER  
1423

NORTH  $\uparrow$

RECEIVED BY  
 Umatilla County Surveyor  
 Date 8-5-86  
 Rec'd By SA  
 No. 86-105-A

T4N-R29 SECT LINES 5/8 + 4/9  
 CORNERS FOUND + Reset  
 BASED ON KIMBRELL'S SURVEYS  
 OF 1910 (BK 2-P. 162)  
 155.1, 1-20-86

86-105-A

76-105-A  
 7N 29 S 5/8  
 6/4