



**NARRATIVE**

The purpose of this survey was to get the corners of Lot 4, Block D of the First Addition to Hermiston. Control was based upon the monuments found as shown along the centerline of W. Orchard Avenue. Bearings are based upon the centerline of W. Orchard Avenue bearing  $589^{\circ}57'00''E$  as determined on County Surveyor Dring. No. R-129-C.

- denotes set  $\frac{3}{8}$  x 30" iron pin with aluminum cap stamped PLS 933
- denotes find concrete nail as called for in County Surveyor Dring. No. K-5-Ax
- ▽ denotes find 3" iron pipe with spike in middle as called for in County Surveyor Drings. No. R-129-C and M-84-Ax. Dring. No. K-5-Ax calls for a 1/2" pipe but this was evidently replaced with a 3" pipe as the distance agrees.

<b>KRUMBEIN ENGINEERING LTD.</b> ENGINEERS - SURVEYORS - PLANNERS 381 S.E. Second Pendleton, Oregon	Scale 1"=30'	Drawn By MLD	Drawn No. 86-188	Revision 1
	Date 7-7-86	Chk. By DMM	Job No. 86-71	Revision 2
Survey for  <b>KALB</b>  Lot 4, Blk D, 1st Add to Hermiston		<b>REGISTERED PROFESSIONAL LAND SURVEYOR</b>  <b>OREGON</b> JULY 17, 1970 <b>DAVID H. KRUMBEIN</b> 933	RECEIVED BY Umatilla County Surveyor Date <u>10-6-86</u> Rec'd By <u>KA</u> No. <u>86-112-A</u>	

86-112-A