



SCALE
1" = 60'

NARRATIVE

This survey, at the request of Ralph & Michelle Schumacher, was to pin the corners of lot 4, blk. 4, of the Blakey Add. to Pendleton, Ore. Located in the S.W. 1/4, Sec.15, T.2N, R.32E, W.M., Umatilla County, Ore. Deed # R108-1257

A field traverse though the Found street mon.s and plat corner showed them to agree with the plat, where proration wasn't necessary. I held plat record to set the pins as shown.

The basis of bearing for this survey is the plat bearing for the centerline tangent at the east-end of S.W. Perkins Ave.

A Topcon GTS 2-B, geodetic total station was used for this survey.

LEGEND

- ⊗ Found 5/8" rebar w/ 1 1/2" Al. cap, stamped P.L.S. 933. Found in position.
- ⊠ Found 5/8" rebar, set by Krumbien. Found in position.
- Found empty mon. can.
- Found 1/2" rebar, set by Krumbien. Found in position.
- ⊙ Set 5/8" rebar w/ plastic cap stamped P.L.S. 346
- ⦿ Set 1/2" rebar w/ plastic cap stamped P.L.S. 346

CURVE DATA

- C-1**
Δ = 79°43'37"
R = 20.00'
T = 16.70'
L = 27.83'
- C-2**
Δ = 19°05'38"
R = 160.00'
T = 26.91'
L = 53.32'
- C-3**
Δ = 30°42'40"
R = 130.00'
T = 35.70'
L = 69.68'

RECEIVED BY

Umatilla County Surveyor
Date 2-98
Rec'd By KK
No. 98-14-A

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Wayne O. Harris

**OREGON
WAYNE O. HARRIS
#346**

WAYNE HARRIS CO., INC.
P.O. BOX 566 PENDLETON, ORE.
541-276-7642

Survey for Ralph & Michelle Schumacher, 327 S.E. 1st #136, Pendleton, Ore. Lot 4, Block 4, Blakey Add.

DWG. T.F. CHK. W.O.H. JB. 97-21 11-24-97

98-14-A