



**SURVEYOR'S NARRATIVE:**

THE PURPOSE OF THIS SURVEY IS TO STAKE THE LINE BETWEEN LOTS 38 AND 39 SO A FENCE CAN BE BUILT.  
 I CONFIRMED THE LOCATION OF THE FOUND IRON REBAR BY RETRACING FERGUSON'S 2000 PLAT OF "ECHO HEIGHTS". THE NORTH IRON REBAR BETWEEN LOTS 38 AND 39 WAS BADLY BENT SO I DROVE A NEW ONE ALONG SIDE OF IT AND PLACED MY YELLOW CAP ON IT.  
 I USED A TOPCON HIPER+ G.P.S. TO CONDUCT THIS SURVEY.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
 JULY 16, 1971  
 G. DENNIS EDWARDS  
 9 5 1  
 RENEWS 12/31/2009

**LEGEND:**

- FND. 5/8" I. REBAR, FERGUSON 2000, PLAT OF "ECHO HEIGHTS," UNLESS NOTED OTHERWISE
- SET 5/8"X30" IRON REBAR WITH PLASTIC CAP #951
- ⊙ COMPUTED LOCATION FROM FERGUSON 2000, PLAT OF "ECHO HEIGHTS"

SURVEY FOR LISA & CHARLES MACK  
 IN LOT 39, "ECHO HEIGHTS," IN SW 1/4,  
 SEC. 9, T 3 N, R 29 E, W.M., UMATILLA  
 COUNTY, OREGON  
 06/15/2011 JOB# S1106041  
 EDWARDS SURVEYING P.O. BOX 763  
 541-567-3336 HERMISTON, OREGON 97838  
 DRAWN BY JMC

**CURVE DATA**

#	RADIUS	ARC	CHORD	DELTA
C1	330.00'	43.20'	N 44°44'56" E 43.17'	07°30'02"
C2	2724.63'	152.89'	N 25°58'50" E 152.87'	03°12'54"

Date: 6-11  
 Drawn by: J.A.  
 No. 11-02-A  
 Umatilla County Surveyor