



SCALE 1" = 200'

● IRON PINS AT ALL CORNERS

C. H. Storms & Associates

CONSULTING ENGINEERS — ARCHITECTS

324 SECOND AVE. SO. TELEPHONE 4170 WALLA WALLA, WASH.

- Mechanical
- Structural
- Hydraulic
- Sanitary
- Designs
- Land Surveys
- House Plans
- Blue Prints
- Estimates

A SURVEY
 FOR
 LESTER L. DUNGAN
 SE 1/4 SEC 1-4N-28E

Date 5/23/51
 Drawn By G.A.H.
 Checked By H.

1263
 SHEET OF

06-626-Ax

702

City Planning
Supervision
Valuation
Surveying
Reports
Designs

C. H. Storms & Associates

CONSULTING ENGINEERS

REGISTERED WASHINGTON, OREGON

C. H. STORMS
Phone 4692-W
G. M. NEWBILL
Phone 2982-M
GEO. LAUBACK
B. F. CHAPMAN
J. O. BICKFORD, Jr.
E. BUCKNER

TELEPHONE 4170
304 Denny Building
WALLA WALLA, WASH.

FILE

Field Notes
Section 1-4N R28E

OWNERS

Mr. Ervin Allen
Mr. Lester Dungan
Mr. Harry Westfall

Having found iron pipes and rock which mark the center of Section 1 4N R28E, the E $\frac{1}{4}$ corner and S $\frac{1}{4}$ corner and South East corner of Section 1. I ran S89°30'E from the S $\frac{1}{4}$ corner on true line and at mid points, between said $\frac{1}{4}$ corner and rock on S.E. corner of said Section, set stake.

From the 3/4" rod at the E $\frac{1}{4}$ corner I ran N89°16'W on true line between said E $\frac{1}{4}$ and 1 $\frac{1}{2}$ " iron pipe at the center of said Section 1. At $\frac{1}{4}$ the distance I found 1" iron pipe at $\frac{1}{2}$ the distance set 5/8" iron rod for 1/16 corner.

Then using our control points I proceeded to set property corners in the S.E. $\frac{1}{4}$ of said Section 1, as shown on these accompanying plats.

G. M. Newbill # 255