

## U. Ernest Nelson & Associates

CONSULTING ENGINEERS

603-612 BUILDERS EXCHANGE BUILDING

Portland 4, Oregon

Telephone ATwater 2057

FIELD NOTES OF SURVEY to establish the boundaries of the S.E. $\frac{1}{4}$  of the N.W. $\frac{1}{4}$  of Sec. 11, T. 4 N., R. 28E., W.M., Umatilla County, Oregon.

This survey was made and used in the laying out of the plats of HERMINSTON PARK Plat No. 1 and HERMINSTON PARK, Plat No. 2.

Both plats were surveyed at the same time, and but one initial Point was used to serve both plats, and the description of each plat is set forth on the plats under the surveyors certificate.

I began survey May 6, 1948 at a concrete monument with bronze cap, having been set for the West  $\frac{1}{4}$  Section corner of section 11, T.4N., R. 28E., W. M., and ran thence N.  $0^{\circ}17'E.$  2647.30 feet to a  $\frac{3}{4}$  inch steel rod, having been set in the pavement for the N. W. corner of said Section 11; I ran thence S.  $89^{\circ}31'E.$  2640 feet to a cedar post, having been set for the North  $\frac{1}{4}$  section corner of said Section 11, the post being badly decayed, I replaced it with a  $\frac{3}{4}$ " iron pipe; I ran thence S.  $0^{\circ}27'15"W.$  2647.10 feet to a 1 inch steel rod marked with a cross on top beside an unmarked stone, having been set for the center of the said Section 11, I ran thence N.  $89^{\circ}31'15"W.$  2632.10 feet to the place of beginning, completing the boundaries of the N.W.  $\frac{1}{4}$  of said Section 11.

By legal subdivision I then established the boundaries of the S.E. $\frac{1}{4}$  of the N. W.  $\frac{1}{4}$  of said Section 11, by beginning at the West  $\frac{1}{4}$  Section corner of said Section 11, and ran S.  $89^{\circ}31'15"E.$  1316.05 feet to the S.W. corner of the S.E. $\frac{1}{4}$  of the N.W. $\frac{1}{4}$  of said Section 11; thence along the legal subdivision line N.  $0^{\circ}22'07"W.$  1323.60 feet to the N.W. corner of the S.E. $\frac{1}{4}$  of the N.W.  $\frac{1}{4}$  of said Section 11; thence along the legal subdivision line S.  $89^{\circ}31'07"E.$  1318.03 feet to the N. E. Corner of the S. E.  $\frac{1}{4}$  of the N. W.  $\frac{1}{4}$  of said Section 11; thence S.  $0^{\circ}27'15"W.$  1323.55 feet to the S. E. corner of the S. E.  $\frac{1}{4}$  of the N. W.  $\frac{1}{4}$  and the center of Section 11 aforesaid; thence N.  $89^{\circ}31'15"W.$  1316.05 feet to the S. W. corner of the S. E.  $\frac{1}{4}$  of the N. W.  $\frac{1}{4}$  of said Section 11.

U. ERNEST NELSON & ASSOCIATES  
BY G. VERNON NELSON  
REGISTERED LAND SURVEYOR NO. 107

*G. Vernon Nelson*