

# CORRECTION SURVEY

OF

RECORDS OF SURVEY FILED FOR  
FRANK & DOLORES LEDBETTER BY TELEK ENGINEERING  
ON LAND LOCATED IN SECTION 36, T5N, R 28 E., W.M.  
UMATILLA COUNTY, OREGON

## STATEMENT OF CORRECTION

A monument was set in the Telek survey for the W. 1/4 corner of section 36 which appears to be superceded by a buried 1" iron pipe reported in the Edwards survey. Although no actual record of the 1" iron pipe has been found, it appears to be of sufficient age to be accepted as the W. 1/4 corner.

## REFERENCES

1. Telek survey for Ledbetter dated 8/78
2. Telek survey for Ledbetter dated 4/79
3. Edwards survey for Bagget dated 7/80

FD. 5/8" I.R. SET IN  
TELEK 8/78 SURVEY



2648.55'  
N00°22'55"E

N 11°48'25"E  
10.43 FT.

FD. 5/8" I.R. SET IN  
TELEK 8/78 SURVEY  
AS W. 1/4 CORNER

FD. 1" IRON PIPE  
STATED IN EDWARDS  
SURVEY TO BE  
"PROBABLY" FROM  
1910 KIMBRELL  
SURVEY

2652.99'  
N00°05'13"E



SCALE: NONE

BEARING BASIS

Telek survey  
reference N<sup>o</sup> 1

FD. B.C.



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
SEPT. 23, 1977  
THOMAS F. LAGIER  
1242

RECEIVED BY

Umatilla County Surveyor

Date 3-81

Rec'd By BLS

No. S-20-Ax

## LEDBETTER CORRECTION SURVEY



TELEK ENGINEERING  
540 SW 11TH STREET  
HERMISTON, OREGON  
97838

DATE	1/16/81	SCALE	NONE
REVISIONS		SHEET	
DRAWN BY	C.D.S.		1 of 1

S-20-Ax