



T6N, R34E, W.M.
1" = 2000

NARRATIVE

The purpose of this survey was to establish the Northwest corner of Section 28, Township 6 North, Range 34 East of the Willamette Meridian. The original GLO surveyor set posts, drove chained stakes, dug pits and raised mound. We searched, but were unable to find any of the original points. Using the points found as shown, I determined that they were usable because of the consistency between them. There is no record of these having been set although they have been used previously as noted.

Bearings are based upon the line between Sections 20-21 and 17-16 being due North

- denotes 1/2 in. x 3/16 in. iron pipe with a 2 in. Brass Cap stamped Umatilla County Surveyor, PLS 988 set
- denotes monument found as noted
- () denotes GLO record bearings and distances

RECEIVED BY
Umatilla County Surveyor
Date 6-82
Rec'd By BLW
No. 82-44-B

John Weidert

KRUMBEIN ENGINEERING CO. ENGINEERS - SURVEYORS - PLANNERS 221 S. Main, Pendleton, Oregon Survey for JOHN WEIDERT	SCALE 1" = 200'
	DATE March 16, 1982
DRN BY ML	CKD BY DJK
DRNG NO 82-116	

located in the NW1/4, NW1/4, Section 28, T6N, R34E, W.M.