



NARRATIVE:

The purpose of this survey to partition Block 7 of Saling's Addition to the City of Weston into four parcels. Control is based upon the original plat of Saling's Addition as recorded in the Plat Books of Umatilla County. All of the blocks are square and we took the plat to indicate that the East edge of Water Street is 20 feet from the center of the section and the other properties were computed from that. The North line of the subdivision is parallel to Main Street and begins 20 feet South of the North quarter corner. The fence lines do not line up with boundaries in the East West direction, but the pins as set do fit the pavement on Franklin Street. Bearings were based on a survey by Krumbert Engineering for the Umatilla County Surveyor in 1983, Um. Co. Surveyor Drwg No. 83-156-C.

- denotes set 3/8" x 30" iron pin with aluminum cap stamped PLS 933
- denotes find Brass Cap, Co. Surveyor No. 83-156-C.

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon	Scale 1"=30'	Drn. By JMS	Drng. No. 85-01C	Revision 1
	Date 7-10-85	Ckd. By MLD	Job No. 84-144	Revision 2
Survey for ROBERT CULLEY		<i>David H. Krumbein</i>		3/15/85 bc 85-28-B
NW 1/4, NE 1/4, Sec. 22, T4 N, R35 E W1				