



**NARRATIVE:**

The purpose of this survey was to divide into two parcels that tract of land belonging to Farm Chemicals Inc. as recorded in Book 275, Page 43 of the Umatilla County Deed Records.

Control for this survey was the Brass Cap of the C/4 of Section 5 and the City of Pendleton monument 519.02 feet North of the S/4 of Section 5 as shown on a survey by Wayne Harris dated 6-22-75, Co. Surveyor No. J-80-B.

The Airport Road was computed from the City of Pendleton data found on the Airport Road Frontage Map, City drawing No. 24-1354.

Bearings are based on the North-South centerline of Section 5 being  $N0^{\circ}51'48''W$  as shown on said Harris survey.

- denotes set  $3/8'' \times 30''$  iron pin with aluminum cap stamped PLS 933
- ⊙ denotes find Brass Cap
- denotes find  $3/8''$  iron pin  $S64^{\circ}06'05''E$  0.98 ft from true position
- ⊙ denotes City of Pendleton monument

|   |                  |                |                     |            |
|---|------------------|----------------|---------------------|------------|
| <b>KRUMBEIN ENGINEERING LTD.</b><br>ENGINEERS - SURVEYORS - PLANNERS<br>361 S.E. Second Pendleton, Oregon | Scale<br>1"=100' | Dwn. By<br>MLD | Drng. No.<br>85-51C | Revision 1 |
|   | Date<br>9-18-85  | Ckd. By<br>DHW | Job No.<br>85-114   | Revision 2 |

  

|   |  |  |
|---|--|--|
| Survey for<br><b>WESTERN FARM SERVICE</b> | REGISTERED PROFESSIONAL LAND SURVEYOR<br><br>OREGON<br>JULY 17, 1979<br>DAVID H. KRUMBEIN<br>933 | RECEIVED BY<br>Umatilla County Surveyor<br>Date <u>10-14-85</u><br>Rec'd By <u>XA</u><br>No. <u>85-131-B</u> |
|---|--|--|

Section 5, T2N, R32E, W.M.