



- 22²³ 27²⁶ 2-75 Harris find B.C. Co. Survey No. J-88-A
1985 Krumbein find B.C.
- 1/4 23²⁴ 26 7-80 Edwards find 1/2" i.r. Co. Survey No. P-140-B
1983 Krumbein find 1/2" iron rod & set B.C.
- 23²⁴ 26²⁵ 1982 K&L find conc. block w/1"x 4 set B.C.
1985 Krumbein find B.C.
- 1/4 24²⁵ 1983 Krumbein set B.C. by single proportionate
between the two section corners.
- 24¹⁹ 25³⁰ 1910 Kimbrell set 2" pipe Book 2 Page 157
1983 Krumbein find 2" pipe & set B.C.
- 1/4 27²⁶ 7-75 Thompson find B.C. Co. Survey No. H-245-Ax
1983 Krumbein find B.C.
- 1/4 29³⁰ 1983 Krumbein set B.C. by single proportionate
between the two section corners.
- 27²⁶ 34³⁵ 7-75 Thompson find 2" ip. Co. Survey No. H-245-Ax
1983 Krumbein find 2" pipe & set B.C.
- 7-80 Edwards set B.C. by double proportion
Co. Survey No. P-140-B
- 26²⁵ 35³⁶ 1983 Krumbein find B.C. and 3/8" i.r. set by Tekk
which bears N51°54'40"E, 24.82 feet
- 25³⁰ 36³¹ 1910 Kimbrell set 2" pipe Book 2 Page 157
1974 Harris set B.C. unable to find 2" pipe at that time
1983 Krumbein find 2" pipe w/1/2" pin in center &
set B.C., also find a B.C. which bears
N08°03'30"E, 44.99 feet from pipe & pin
- 1/4 31³⁵ 1983 Krumbein find 3/4" pipe (no record) & set B.C.
- 8-78 Tekk set 5/8" i rod Co. Survey No. P-92-C
4-74 Edwards find angle iron Co. Survey No. M-20A
1983 Krumbein find pipe & 1/2" rod & set B.C.
- NE 1/4 Sec 36 4-79 Krumbein set B.C. Co. Survey No. Q-1101-B
1983 Krumbein find B.C. & reset in correct position 5 19°36'45"W 20.73 ft. from 1979 position
- N 1/4 Sec 36 4-79 Krumbein set B.C. Co. Survey No. Q-1101-B
1983 Krumbein find B.C. & reset in correct position 5 51°31'33"W 13.63 ft. from 1979 position
- E 1/4 Sec 36 4-79 Krumbein set B.C. Co. Survey No. Q-1101-B
1983 Krumbein find B.C. & reset in correct position 5 63°42'34"W 8.20 ft. from 1979 position
- E 1/4 Sec 36 4-79 Krumbein set B.C. Co. Survey No. Q-1101-B
1983 Krumbein find B.C. & reset in correct position 5 64°57'37"W 4.28 ft. from 1979 position
- 1/4 36³¹ 5-76 Edwards find 2" pipe Co. Survey No. H-95-B
1983 Krumbein find 2" pipe & set B.C.
2" pipe originally set by Kimbrell
Book 2 Page 157

- 5 1/2 1910 Kimbrell set 2" pipe Book 2 Page 157
- 34³¹ 1983 Krumbein find 2" pipe & set B.C.
- 34³⁵ 7-80 County set B.C. Co. Survey No. S-156-C
1983 Krumbein find B.C.
- 35³⁶ 7-80 County set B.C. Co. Survey No. S-156-C
1983 Krumbein find B.C.
- 5 1/4 7-80 County set B.C. Co. Survey No. S-156-C
5c. 36 1983 Krumbein find B.C. & reset in correct position
- 36³¹ 7-80 County set B.C. Co. Survey No. S-156-C
6 1983 Krumbein find B.C. & reset in correct position
based on Kimbrell survey of 3-31-1910
Book 2 Page 171
- 36 7-80 County set B.C. Co. Survey No. S-156-C
1 1/6 1983 Krumbein find B.C.
- 31 1983 Krumbein find 3/8" iron rod, set by W.W.
6 5 Cramer
- 31³² 1983 Krumbein find R.R. spike, set by W.W.
5 Cramer
- W 1/4 1910 Kimbrell set stone
5c. 36 1983 Krumbein find 1 1/2" i pipe & replaced
with B.C.

- denotes Brass Cap as noted
- denotes monument find as noted
- denotes set 5/8" i pin with aluminum cap stamped PLS 933

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon		Scale 1"=1000 Date 6-27-83	Dwn. By M.L.D. Ckd. By D.H.K.	Dwg. No. 83-35C Job No. 82-29	Revision 1 12-20-83 Revision 2 2-20-84
Survey for UMATILLA COUNTY SURVEYOR T5N, R28E, W.M.			REGISTERED PROFESSIONAL AND SURVEYOR OREGON JULY 17, 1970 DAVID H. KRUMBEIN 933	RECEIVED BY Umatilla County Surveyor Date: 6-5-8 Rec'd by: [Signature] No. 88-27-B	