



NARRATIVE

The purpose of this survey was to establish the boundaries of a parcel belonging to Robert Wright. This 100 foot wide strip extends from the old City of Walla Walla Waterline to the Center of Section 21. The Old Waterline has been abandoned but has been tied down in the past and is still in place. The Center of Section 21 has not been determined. Only one acceptable section corner has been found in T6U, R38E. The Bureau of Land Management is currently surveying the entire township but has not been able to find or establish any corners.

The East and West lines of the parcel were established from an old fence line that we found on the hillside above the creek. The two fences found were 502 feet apart so I tied the fence on the West side of the Struthers property as more of it was found. Then the 200 foot and three 100 foot parcels were laid out from that West fence line.

The Federal Highway Administration surveyed along Mill Creek Road in 1985. They tied to control established by this firm, County Surveyor No. 84-41C. The two points X-36 and X-37 set by FHWA were reset from references and the bearing between the two of N 79° 21' 39" E was used to control the survey. The bearings were then adjusted to True Bearings by using a \ominus angle.

• denotes set 3/8" x 30" iron pin with aluminum cap stamped PLS 933

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 381 S.E. Second Pendleton, Oregon	Scale 1" = 40'	Drawn By MLD	Drawn No. 88-20C	Revision 1
	Date 10-27-88	Checked By DHK	Job No.	Revision 2
Survey for ROBERT S WRIGHT		REGISTERED PROFESSIONAL LAND SURVEYOR David H. Krumbey	OREGON JULY 17, 1979 DAVID H. KRUMBEIN 933	
SW1/4, NW1/4, Sec. 21, T6U, R38E, N.M.		No. 88-76-B		