



HISTORY

- GEORGE S. PERSHIN, UNDER GLO CONTRACT NO. 361 DATED 1881, SURVEYED THE STANDARD PARALLEL BETWEEN T.5S., R.30E. AND T.6S., R.30E. FRANK CAMPBELL, UNDER GLO CONTRACT NO. 380 DATED 1881, SURVEYED T.6S., R.30E.

- IN 1976, OREGON PLS 598 REMONUMENTED THE FOLLOWING CORNERS FROM ORIGINAL EVIDENCE: T.6S., R.30E. - SW S33, S1/4 S34, SW S35; T.5S., R.30E. - NW CC S1, NW CC S2, AND NW CC S3.

- IN 1977, OREGON PLS 933 REMONUMENTED THE FOLLOWING CORNERS FROM ORIGINAL EVIDENCE: T.6S., R.30E. - S1/4 S35 AND S6 S36. BEARINGS WERE BASED ON POLARIS OBSERVATIONS. HE THEN SUBDIVIDED PORTIONS OF SECTIONS 1, 2 AND 3 IN T.6S., R.30E. HIS SURVEY WAS RECORDED IN 1977 IN UMATILLA COUNTY AS M-64.

NOTES

- BEARINGS WERE BASED ON THE COMPUTED BEARING BETWEEN THE SW S33 AND E1/4 S1 TAKEN FROM THE PLAT FILED BY PLS 933.

- BEARINGS AND DISTANCES SHOWN ON THE DRAWING ABOVE ARE FROM THE FOLLOWING SOURCES:
 GLO - COPIES OF ORIGINAL SURVEY DOCUMENTS.
 PLAT - COPIES OF THE PLAT FILED BY PLS 933 IN 1977 IN UMATILLA COUNTY AS M-64.
 SURV - COMPUTATIONS BASED ON THE RAW DATA OF THIS SURVEY BETWEEN RECOVERED MONUMENTS.
 TRUE - CALCULATIONS FOR THE STANDARD PARALLEL BETWEEN THE CORNERS LISTED IN 'HISTORY' ABOVE AS REMONUMENTED FROM ORIGINAL EVIDENCE BY PLS 598 AND PLS 933.

- FOR ADDITIONAL INFORMATION ON CORNERS FOUND OR MONUMENTED BY THIS SURVEY, SEE THE 'CERTIFIED RECORD OF LAND CORNER MONUMENTATION' FORMS FILED BY PLS 598 AND PLS 933 AND THOSE FORMS FILED WITH THIS PLAT.

- FIELD BOOK REFERENCE IS TRAVERSE BOOK 2 OF THE JUNIPER 1988 CADASTRAL SURVEY.

SURVEYOR'S CERTIFICATION

I, DAVID L. HADDOCK, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF OREGON, HEREBY CERTIFY, THAT THIS PLAT AND THE NOTES HEREON, OR ATTACHED, ARE A CORRECT REPRESENTATION OF A SURVEY PERFORMED UNDER MY DIRECT SUPERVISION DURING THE MONTHS OF JUNE, OCTOBER AND NOVEMBER OF 1988, AT THE REQUEST OF THE USDA FOREST SERVICE, IN ACCORDANCE WITH STATUTES OF THE STATE OF OREGON AND WITH THE ARTICLES OF THIS CONTRACT.

David L. Haddock
 DAVID L. HADDOCK
 OREGON LICENSE NO. 852

REGISTERED PROFESSIONAL LAND SURVEYOR
 David L. Haddock
 OREGON JAN 15 1989
 DAVID L. HADDOCK
 852

NARRATIVE

THIS SURVEY WAS PERFORMED AT USDA FOREST SERVICE REQUEST DURING JUNE, OCTOBER AND NOVEMBER OF 1988. THE PURPOSE OF THE SURVEY WAS TO POST THE BOUNDARIES OF NATIONAL FOREST SYSTEM LANDS AS SHOWN IN THIS DRAWING. DUE TO ERRORS IN THE PREVIOUS SURVEY EVIDENT IN REVIEW OF THE FILED PLAT, M-64, FOUR CORNERS WERE MONUMENTED. THESE CORNERS WERE ALL SET ON THE STANDARD PARALLEL. THE S1/4 OF S33 WAS LOCATED BY SINGLE PROPORTION BETWEEN THE THE SW CORNER OF S33 AND THE S1/4 OF S34. THE NW CLOSING CORNERS OF SECTIONS 1, 2 AND 3 WERE SET AT THE INTERSECTION POINTS OF THE STANDARD PARALLEL AND LINES PASSING THROUGH THE REMONUMENTED CLOSING CORNERS WITH THE BEARINGS GIVEN ON THE PLAT M-64 BY PLS 933.

ALL EXISTING BRASS CAPS ALONG THE STANDARD PARALLEL WERE SURVEYED AS CONTROL POINTS. THE POSITIONS OF THE SW OF S33 AND THE E1/4 OF S1 WERE FOUND TO BE WITHIN 0.25' IN 15000'. THIS INDICATED ADEQUATE CLOSURE OF THE SURVEY. THE SURVEY WAS MADE USING A WILD T2E THEODOLITE AND A WILD DI 1000 EDM. THIS SURVEY IS DEPICTED ON A SURVEY CONTROL DIAGRAM GIVEN TO THE FOREST SERVICE COR. THE BOUNDARIES OF NATIONAL FOREST SYSTEM LANDS WERE POSTED WITH 6" STEEL POSTS AND FOREST SERVICE BOUNDARY SIGNS.

TOWNSHIPS 5 AND 6 SOUTH, RANGE 30 EAST
 WILLAMETTE MERIDIAN
 RETRACEMENT OF STANDARD PARALLEL
 JUNIPER 1988 CADASTRAL SURVEY
 UMATILLA COUNTY, OREGON
 UMATILLA NATIONAL FOREST
 CONTRACT NO. 00-04R3-8-44
 FIRST STANDARD PARALLEL SOUTH

EXAMINED AND ACCEPTED FOR THE U.S. FOREST SERVICE
 THIS 17th DAY OF JANUARY, 1989.
 Dennis F. Jay Lovel C.D.R.
 I CERTIFY THAT THIS SURVEY WAS PERFORMED AT THE REQUEST OF THE UMATILLA NATIONAL FOREST.
 NATIONAL FOREST SUPERVISOR 1-17-89
 DATE