


- LEGEND:**
- Found monuments, as noted.
  - ⊙ 2 1/2" Brass Cap, Found as noted.
  - Set 5/8" x 30" rebar with plastic cap #951.
  - (000) of Record. Fraley survey, No Date.
  - [000] of Record. Deeds.
  - {000} of Record from 1932 Supplemental G.L.D. survey.

HOWARD, B. 330, Pg. 132.



No.	Radius	Arc	Chord	Delta
A	SPARAL	226.76'	S 11°12'43"E 226.76'	
B	SPARAL	171.49'	S 10°09'08"E 171.49'	
C	5679.58	404.12'	S 7°22'57"E 404.03'	4°04'36"
D	5679.58	126.85'	S 4°42'10"E 126.85'	1°16'47"

TRACT I  
30.92 Ac.

DETAIL: N.T.S.

**NARRATIVE:**

The purpose of this survey is to stake the corners of that tract of land deeded to Peter and Martha Edmiston on Reel 140, Page 852, Umatilla County Deed Records, so a fence can be built and to show the location of two wells and of highway access points.

I found monuments at 7 of the 12 corners of the two tracts of this property. A search of the County Surveyor's office did not find any surveys showing any of those monuments. Edmiston's deed and the deeds of the adjacers call for all of the found monuments which indicates to me that there were surveys done that did not get recorded. I held the found monuments except for the most southerly Southeast corner which I held for Eastings and set on the 1/2" line for Northings. I based the bearings on the deed call for the line common to Edmiston and Burke.

REGISTERED PROFESSIONAL LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
S.S.I.  
RENEWS 12/31/97

RECEIVED BY

Umatilla County Surveyor

Date: 12-97

Rec'd by: KR

No. 97-249-B

Survey for MARTHA EDMISTON  
in the NE 1/4 Section 3, T4N, R28E, W.M.,  
Umatilla County, Oregon  
11/10/97 Rev. 11/12/97 Job #59710260  
Edwards Surveying P.O. Box 763  
541-567-3336 Hermiston, Oregon 97830