



FND 5" PINE TREE AS NOTED ON C.S. NO. 88-11B, WITH 5/8" REBAR ON SOUTH SIDE 2003 - TREE 14"

NE COR, SE 1/4, NW 1/4

SCALE: 1" = 100'

**LEGEND**

- INDICATES FND. 5/8" IRON REBAR W/ STATE PARKS PLASTIC CAP
- INDICATES FOUND MONUMENT AS NOTED OR FND 5/8" I. REBAR W/ALUM CAP.PLS933
- INDICATES SET 5/8" BY 30" IRON REBAR W/ ALUMINUM CAP STAMPED PLS 933
- ▲ FOUND REBAR OF UNKNOWN ORIGIN

COURSE	BEARING	DISTANCE
L1	N 15°31'18"E	53.86'
L2	N 29°16'07"E	49.14'
L3	N 02°17'28"E	52.75'
L4	N 45°00'00"W	38.02'
L5	N 15°31'18"E	46.44'
L6	N 29°16'07"E	51.53'
L7	S 67°18'34"W	68.48'
L8	S 72°03'10"W	23.60'
L9	S 68°20'23"W	46.84'
L10	S 45°37'25"W	70.00'

**NARRATIVE**

PURPOSE OF THIS SURVEY IS TO MONUMENT THE REVISED BOUNDARIES BETWEEN BEININGEN, BLISS AND BETTY CRITCHLOW. THE PROPERTY AROUND THE BEININGEN AND BLISS PROPERTIES BELONGS TO CRITCHLOW AND THE PARTIES AGREED TO TRANSFER DEEDS TO MATCH THE OCCUPIED LINES. THE LEGALS ARE WRITTEN AND WERE RECORDED IN NOVEMBER OF 2004. I PREVIOUSLY SURVEYED THE SURROUNDING PROPERTIES AS INDICATED AND THIS SURVEY TIES TO PREVIOUS WORK. THE NORTH-SOUTH CENTERLINE OF THE SECTION IS THE BASIS OF

<b>KRUMBEIN ENGINEERING LTD.</b> ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon	Scale 1"=100'	Dwn. By H-P	Drng. No. 05 04 C
	Date 1-31-05	Chk. By DNK	Job No. 8966

PROPERTY LINE RESURVEY

**CRITCHLOW**

SE 1/4, NW 1/4,  
SECTION 20  
T.1N., R.35.E.W.M.  
UMATILLA COUNTY, OR

*David H. Krumbein*

RECEIVED BY  
Umatilla County Surveyor  
Date: 2-05  
By: KR  
No. 05-16-B