



BLOCK O & P

ORIGINAL TOWN OF UKIAH

SCALE 1" = 100'

AUGUST 3, 1947

REGISTERED  
OREGON  
LAND SURVEYOR  
*Elmer E. Robert*  
ELMER E. ROBERT  
169

Q-1263-B  
9-1263-B  
5531

Q-1263-B

# ELMO E. ROBNETT

*Registered Land Surveyor*

Box 0176  
MILTON, OREGON

SURVEY FOR SCHOOL DISTRICT # 80  
Block P & O-Original Town  
of Ukiah, Umatilla County,  
Oregon

The center monument of Section 14 T5 S, R31 E has been hit by a truck and moved.

Searched for original monuments at the corners of the Plaza Block of the Original Town; found a rock monument at the Southwest corner of said Plaza Block.

Parol evidence that the Ukiah Mercantile Building had been carefully surveyed in when built. Checked from the corner of the Church and from the found corner.

Set an iron pin 40 feet from the Southeast corner of said Ukiah Mercantile Building in line with the front of Hotel; checked for Right angles and distance to the original monument.

Ran North on the produced line 530 feet to the North line of Hill Street.

Ran lots 1,2,7 & 8, Block P and Block O according to the recorded Plat thereof.