



NARRATIVE:

The purpose of this survey was to establish the centerline of Walnut Street at the request of the City of Echo.
 Walnut Street is a part of the Plot of Westlawn Addition to Umatilla County. The plot shows a distance of 703 feet to the Northwest corner of the Southwest corner of Section 16. It was not clear on the plot what the bearing was so I made the assumption that it should be along the East-West centerline of the section.
 County Surveyor Drwg. No. 5-153-C, shows the breakdown of Section 16. We tied to two of the corners on that survey, and computed over the called for distance to the West line of the subdivision.
 I took the information on the plot to indicate that the angles were all 90° and the streets were 60 feet wide. Using that information, we established the centerline of Walnut Street as shown.
 Bearings are based on County Surveyor Drwg. No. 5-153-C.

• denotes set "1/8" x 30" iron pin with aluminum cap stamped RIS 933

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon		Scale 1"=20' Date 6-27-85	Dwn. By MLD Ckd. By DHH	Drwg. No. 85-18-D Job No. 85-77	Revision 1 Revision 2
Survey for CITY OF ECHO Section 16, T3N, R29E, W.M.		REGISTERED PROFESSIONAL LAND SURVEYOR <i>David H. Krumbain</i> LEVITON K. KRUMBEIN		RECEIVED BY Umatilla County Surveyor Date 1-10-86 Rec'd by <i>ME</i> No. 86-8-C	

VICINITY MAP
1"=100'