



Total area = 86.74.
 Unusable Area = 2.24
 Remaining Acreage = 84.50

NARRATIVE

The purpose of this survey was to define an 84.5 tillable acre tract located in the NW 1/4 of Section 8, T5N, R33E, W.M. The North line of the parcel is the North line of Section 8 and the West line of the parcel is the East right-of-way line of County Road No. 863 (Butler Grade).
 The North line of the NW 1/4 of Section 8 was established by using a stone set by Arnold in 1892 at the 1/4 corner common to Sections 5 and 8. The NW corner of Section 8 was established using Arnold's distance and the plow lines locally accepted as the section corner. The West line of the NW 1/4 of Section 8 was accepted as the centerline of existing roadway bounded by plowlines, this is County Road No. 863 (Old No. 112) of which the described centerline is also the section line common to Sections 7 and 8, T5N, R33E, W.M.
 The South and East lines were placed so as to establish the 84.5 tillable acres, taking out the 2.24 acres of unusable ground and the 1.43 acres of right-of-way. Bearings are based on Arnold's survey setting the North line of the Section due West. Arnold's survey is in Surveyor's Court, Survey No. 52, 1892.

- denotes set 3/8" x 30" iron pin with aluminum cap stamped PLS 933
- denotes set 2" Brass Cap on a 1/2" x 30" galvanized iron pipe

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon	Scale 1"=100'	Drawn by MLD	Dwg. No. 86-050	Revision 1
	Date 7-2-86	Check by DHA	Job No. 86-56	Revision 2
Survey for TERJESEN			RECEIVED BY Umatilla County Surveyor Date 10-6-86 Rec'd By [Signature] No. 86-119-C	
NW 1/4, Sec 8, T5N, R33E, W.M.				