



**LEGEND**

- PUBLIC LAND SURVEY MONUMENT OF RECORD ON SURVEY NO. 90-50-C. SEE RECORDED MAP AND CORNER RECORDS.
- RE-ESTABLISHED CORNER AND REMONUMENTED WITH A 2 1/2" BRASS CAP ON A 1 1/4" G.I.P., UNLESS OTHERWISE NOTED. SEE CORNER RECORD FILED SEPARATELY.
- FOUND CORNER OR MONUMENT AS NOTED.
- FOUND MONUMENT AND REMONUMENTED WITH A 2 1/2" BRASS CAP ON A 1 1/4" G.I.P., UNLESS OTHERWISE NOTED. SEE CORNER RECORD FILED SEPARATELY.
- THE LETTER "M" BESIDE A CORNER MONUMENT SYMBOL INDICATES THE CORNER MONUMENT WAS MAINTAINED DURING THIS SURVEY. SEE CORNER RECORD FILED SEPARATELY.
- FOUND A 2 1/2" BRASS CAP ON A 2" G.I.P. FROM L.E. WILKES SURVEY IN 1917.
- RECORD FROM SURVEY NO. 90-50-C.
- RECORD FROM GLO CONTRACT NO. 92. (J. BURNETT, 1860)
- RECORD FROM GLO CONTRACT NO. 107. (DANIEL CHAPLIN, 1864)
- RECORD FROM GLO SPECIAL CONTRACT DATED MAY 4, 1887, BY CURRIN AND NOLAND. SURVEYED IN 1887.
- RECORD FROM THE RESURVEY OF THE SUBDIVISION LINES OF PORTIONS OF T2N, R32E, W.M., UNDER SPECIAL CONTRACT DATED MAY 4, 1887. PERFORMED BY CURRIN AND NOLAND IN 1890.
- RECORD FROM GLO RETRACEMENT AND RESURVEY BY L.E. WILKES IN 1917.
- RECORD FROM SURVEY NO. R-28-B.

**NARRATIVE OF SURVEY**

THE PURPOSE OF THIS SURVEY WAS TO RECOVER, RE-ESTABLISH, REMONUMENT OR MAINTAIN CERTAIN SECTION AND 1/4 SECTION CORNERS IN SECTIONS 13 THROUGH 18 OF TOWNSHIP 2 NORTH, RANGE 32 EAST, W.M. THE SURVEY WORK WAS AUTHORIZED BY THE UMATILLA COUNTY BOARD OF COMMISSIONERS AND FUNDED BY THE PUBLIC LAND CORNER MONUMENTATION FUND.

INFORMATION RECORDED IN THE COUNTY SURVEYOR'S OFFICE FOR THIS PROJECT INCLUDES THIS MAP OF SURVEY AND LAND CORNER RECORDS FOR CORNERS IMPROVED TO CURRENT STANDARDS.

SURVEYS WERE MADE WITH A WILD T-16 THEODOLITE AND MAG II-H INFRARED DISTANCE METER, A NIKON NTD 2 SEMI-TOTAL STATION AND A LIETZ SET 88 TOTAL STATION. CORNER MONUMENTATION AND MAINTENANCE MEASUREMENTS WERE MADE WITH A BRUNTON POCKET TRANSIT AND STEEL TAPE.

BEARINGS ARE BASED ON THE CITY OF PENDLETON LOCAL GRID. SURVEY MEASUREMENTS SHOWN ON THE MAP ARE NOT ADJUSTED. A SLIGHT MIS-CLOSURE EXISTS IN SECTIONS 17 AND 18 BECAUSE MEASUREMENTS WERE NOT ADJUSTED TO CLOSE ON RECORD MEASUREMENTS FOR PREVIOUS SURVEY NO. 90-50-C. THIS SLIGHT MIS-CLOSURE DOES NOT AFFECT THE INTEGRITY OF ANY RE-ESTABLISHED CORNER BECAUSE THE MEASURED COORDINATES WERE USED FOR POSITION CALCULATIONS.

HISTORY OF SURVEYS:

SURVEYS IN THE TOWNSHIP BEGAN IN 1860 WITH THE SURVEY OF THE TOWNSHIP EXTERIORS. IN 1864, DANIEL CHAPLIN SUBDIVIDED THE ENTIRE TOWNSHIP. IN 1871, Z.F. MOODY ESTABLISHED THE BOUNDARIES OF THE UMATILLA RESERVATION AND RESUBDIVIDED SECTIONS WITHIN THE RESERVATION. MOODY'S SURVEY WAS MADE INDEPENDENTLY, WITHOUT RECOVERY OF CORNERS ESTABLISHED BY DANIEL CHAPLIN. IN 1887 AND 1890, CURRIN AND NOLAND INDEPENDENTLY RESURVEYED THE RESERVATION BOUNDARY AND SECTIONS WITHIN THE RESERVATION. CURRIN AND NOLAND RECOVERED AND REMONUMENTED MANY OF MOODY'S CORNERS. CURRIN AND NOLAND ALSO SURVEYED THE DIMINISHED RESERVATION BOUNDARY. IN 1917, L.E. WILKES RESURVEYED THE WEST LINE OF THE DIMINISHED RESERVATION BOUNDARY. RECORD OF PRIVATE SURVEYS, BOOKS 1 AND 2, CONTAIN RETRACEMENTS, SECTION SUBDIVISIONS AND SURVEYS FOR SOME SECTIONS IN THE TOWNSHIP. THE PRIVATE SURVEY BOOK RECORD IS SHOWN ON THIS MAP IF APPLICABLE.

LAND CORNER RECORD FORMS: THE LAND CORNER RECORD FORMS, FILED SEPARATELY, CONTAIN EXPLANATIONS, HISTORIES AND METHODS OF RE-ESTABLISHMENT FOR CORNERS VISITED ON THIS SURVEY. THE LAND CORNER RECORDS SHOULD BE CONSULTED FOR SPECIFIC INFORMATION ON EACH CORNER.

REGISTERED PROFESSIONAL LAND SURVEYOR  
 WILLIAM R. WELLS  
 OREGON JULY 22, 1977  
 WILLIAM R. WELLS 1106

WILLIAM R. WELLS, PLS  
 357 N.E. HWY. 11  
 P.O. BOX 1696  
 PENDLETON, OR 97801  
 PHONE: (503) 276-6362

PROJECT:  
 PUBLIC LAND CORNER  
 REMONUMENTATION  
 FOR  
 UMATILLA COUNTY.  
 SECTIONS 13 THROUGH 18  
 T2N, R32E, W.M..

RECEIVED BY  
 Umatilla County Surveyor  
 Date: 8-92  
 Rec'd By: KR  
 No. 92-92-C

DATE: AUG. /92 DR. BY: MEQ  
 CK. BY: WRW NO: 42-129