



• INDICATES 5/8\" I. PIN SET
 NOTE: BEARINGS ARE BASED UPON TIES TO C.G.S. POINTS "STANFIELD WEST BASE" AND "IRRIGON". BEARINGS SHOWN ARE TRUE.
 COORDINATES GIVEN ARE "OREGON NORTH ZONE"

STATION	NORTH	EAST
NE 25	782213.06	2287822.10
SE 25	776922.69	2287874.64
SW 25	776849.83	2282598.66
NW 25	782146.67	2282239.44
N 1/4 25	782179.86	2285180.79
NE P.C.	782192.81	2287802.30
SE P.C.	780841.86	2287815.71
SW P.C.	780139.79	2285202.30
NW P.C.	782159.86	2285180.98

GRID NORTH
 TRUE NORTH
 TRUE NORTH = GRID NORTH + 0° 47' 52"
 TRUE DIST. = GRID DIST. + .3999332

RR E
 1° C.R.
 Δ = 24° 33'
 R = 6279.64
 T = 1365.61

12-30-74	REVISED COORDINATES	DES
12-6-71	REVISED COORDINATES	DHK
WAYNE HARRIS CO. INC.		
SURVEY FOR PORT OF UMATILLA SECTION 25, T.4N., R.27E. W.M.		
SCALE 1" = 300'	DATE 11-29-71	DRN. BY DHK
		DRNG. NO. 71-288 C

REGISTERED
 OREGON
 LAND SURVEYOR
 David H. Krumbein
 JULY 17, 1970
 DAVID H. KRUMBEIN
 933

03-294-C