

GPS CONTROL STATION

OREGON STATE PLANE, NORTH ZONE

STATION NAME: 72	GEODETIC COOR: NAD 83(91):
SECTION: NW 1/4, S3, T.2N., R.32E., UMATILLA COUNTY, OREGON	LAT: 45°41'20.11074" N LONG: 118°48'26.66146" W
DATE SET: MARCH 1996	STATE PLANE CO-ORDINATES, NAD 83-91, INT.FT.:
SURVEYOR: WILLIAM R. WELLS PLS 1106	N: 741800.686 E: 8634608.359 THETA: 1°12'01.31"
FIRM: WILLIAM R. WELLS, LAND SURVEYING AND PLANNING P.O. BOX 1696 PENDLETON, OR 97801 (541) 276-6362	SCALE FACTOR: 0.99993578 ELEV: 1428.49 US.FT. ELEV. DATUM: LOCAL, CITY OF PENDLETON
ORDER: SECOND ORDER, CLASS I	CITY OF PENDLETON CO-ORDINATES INT.FT.:
	N: 57549.875 E: 42493.539

LOCATION:

STATION IS ON EAST SIDE OF HOLDMAN ROAD SOUTH OF NELSON RANCH.
FROM EAST PAVED TURNOUT STATION IS NORTH 70° WEST, 1500 FEET M/L.
STATION IS SOUTH 64° EAST FROM CORNER MONUMENT FOR SECTIONS 3 AND
4.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP MARKED
"OR PLS 1106, WA PLS 17372".

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-96