

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9332

QUARTER SECTION: SW

GEODETIC COOR: NAD 83(91)

SEC. 24 TWP.4 N,RGE.28E  
UMATILLA CO.ORE.

LAT: 45°48'47.41275" N

DATE SET: JULY ,1993

LONG: 119°16'14.27266" W

SURVEYOR: WALTER L. CASWELL  
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP  
13545 NW SCIENCE PARK DR  
PORTLAND, OR. 97229  
(503) 643-1073

N: 784960.899 INT.FT.

E: 8515561.849 INT.FT.

THETA: 0°52'18.663"

TYPE: GPS

SCALE FACTOR: 0.999957866

ORDER: SECOND, CLASS: 1

ELEV: 645.159 US.FT.

ELEV. DATUM: NGVD 29

\*\*\*\*\*  
DIRECTIONS "TO REACH"

FROM THE INTERSECTION OF HWY. 395 AND FEEDVILLE ROAD, TRAVEL WEST ON FEEDVILLE ROAD 1.0 MILE TO A PAVED SIDE ROAD NORTH. GO NORTH ON SAID SIDE ROAD 0.5 MILE 25 FEET PAST SIDE ROAD EAST. THEN TRAVEL WEST ON DIRT PATH 0.05 MILE TO POWER POLE 241502 AND POINT OF CURVE IN PATH. CONTINUE WEST CROSS COUNTRY 0.2 MILE PAST 1/4 SECTION MONUMENT AND 7' X 4" PIPE TO MONUMENT.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 0.25 MILE WEST OF CENTERLINE OF SIDE ROAD, ON APPROXIMATE 1/4 SECTION LINE.

METERS X 3.28083333333 = U.S. FEET  
METERS X 3.28083989501 = INTERNATIONAL FT.

