

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9306

QUARTER SECTION: SE

GEODETTIC COOR: NAD 83(91)

SEC. 9 TWP.5 N,RGE.28E  
UMATILLA CO.ORE.

LAT: 45°55'21.41121" N

DATE SET: JULY ,1993

LONG: 119°18'49.74308" W

SURVEYOR: WALTER L. CASWELL  
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP  
13545 NW SCIENCE PARK DR  
PORTLAND, OR. 97229  
(503) 643-1073

N: 824700.742 INT.FT.

E: 8503965.187 INT.FT.

THETA: 0°50'28.406"

TYPE: GPS

SCALE FACTOR: 0.999981245

ORDER: SECOND, CLASS: 1

ELEV: 314.399 US.FT.

ELEV. DATUM: NGVD 29

\*\*\*\*\*  
DIRECTIONS "TO REACH"

FROM THE OVERPASS OF HWY. 395 (I-82) (MCNARY HWY.) OVER HWY. 730 (COLUMBIA RIVER HWY.), GO EASTERLY ON 730 0.20 MILE TO A PAVED SIDE ROAD TO THE NORTH (SPRAGUE RD.). GO NORTHERLY ON SAID CROSS ROAD 0.5 MILE TO ITS INTERSECTION WITH THE RAILROAD TRACKS. FOLLOW THE TRACKS TO THE WEST 0.3 MILE TO MONUMENT.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 13 FEET SOUTH OF RAILROAD TRACKS, 30 FEET NORTH OF RIGHT-OF-WAY FENCE.

METERS X 3.28083333333 = U.S. FEET  
METERS X 3.28083989501 = INTERNATIONAL FT.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Walter Caswell*

OREGON  
JULY 8, 1968  
WALTER L. CASWELL  
737

*Exp. 12/31/93*