

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9309

QUARTER SECTION: SE

GEODETIC COOR: NAD 83(91)

SEC. 16 TWP.5 N,RGE.28E  
UMATILLA CO.ORE.

LAT: 45°54'43.00918" N

DATE SET: JULY ,1993

LONG: 119°18'23.60298" W

SURVEYOR: WALTER L. CASWELL  
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP  
13545 NW SCIENCE PARK DR  
PORTLAND, OR. 97229  
(503) 643-1073

N: 820838.499 INT.FT.

E: 8505870.362 INT.FT.

THETA: 0°50'46.944"

TYPE: GPS

SCALE FACTOR: 0.999978804

ORDER: SECOND, CLASS: 1

ELEV: 444.655 US.FT.

ELEV. DATUM: NGVD 29

\*\*\*\*\*  
DIRECTIONS "TO REACH"

FROM THE INTERSECTION OF HWY. 395 (UMATILLA-STANFIELD HWY.) AND MARGARET AVE. (A DIRT ROAD ON THE NORTH SIDE OF POWER CITY), GO WEST ON MARGARET AVE. 0.1 MILE TO A GRAVEL DRIVE ACCESS TO A MOBILE HOME AREA.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP INSCRIBED "BUFORD ASSOC. PLS 1148". STATION IS 25 FEET NORTH OF ROAD, 9 FEET SOUTH OF BARB WIRE FENCE.

METERS X 3.28083333333 = U.S. FEET  
METERS X 3.28083989501 = INTERNATIONAL FT.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Walter Caswell*

OREGON  
JULY 8, 1966  
WALTER L. CASWELL  
737

*Exp. 12/31/93*