

TOMKINS LAND SURVEYING, INC.  
20 EAST POPLAR, SUITE 204  
WALLA WALLA WA 99362  
PHONE: 509/522-4843  
FAX 509/522-1902  
email: tomkins@wwics.com

---

**JUNE 17, 1998**

**HORIZONTAL CONTROL DATA**

**STA. NAME:** 1051

**LOCATION:** TOWNSHIP 5 NORTH, RANGE 35 EAST, WILLAMETTE MERIDIAN. CORNER COMMON TO SECTIONS 1, 2, 11 & 12.

**DESCRIPTION:** RAILROAD SPIKE WITH A PUNCH MARK AT THE INTERSECTION OF DEHAVEN AND 2<sup>ND</sup> AVENUE..

**GEODETTIC COORDINATE:** NAD 83(91)

**LAT:** 45°55'58.98578" N.

**LONG:** 118°23'34.17396" W.

**STATE PLANE COORDINATE:** NAD 83(91) OREGON NORTH ZONE (3601)

**N:** 253984.487 METERS

**E:** 2663404.197 METERS

**N:** 833282.408 INT. FEET

**E:** 8738202.760 INT. FEET

**ELEVATION:** 315.50 METERS

1035.10 FEET

**ELEVATION DATUM:** NAVD 88

**THETA:** 1°29'39.8"

**GRID FACTOR:** 0.999983667

**SEA LEVEL FACTOR:** 0.999950491

**COMBINED SCALE FACTOR:** 0.999934158

**CONVERSION:**

METERS X 3.28083333333 = U.S. FEET

METERS X 3.28083989501 = INTERNATIONAL FEET

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Greg E. Flowers*  
OREGON  
JUNE 30, 1997  
GREG E. FLOWERS  
02620LS

RENEWS 12/31/99

6/17/98