

TOMKINS LAND SURVEYING, INC.
20 EAST POPLAR, SUITE 204
WALLA WALLA WA 99362
PHONE: 509/522-4843
FAX 509/522-1902
email: tomkins@wwics.com

JUNE 17, 1998

HORIZONTAL CONTROL DATA

STA. NAME: 902

LOCATION: TOWNSHIP 6 NORTH, RANGE 35 EAST, WILLAMETTE MERIDIAN. S.W. 1/4 OF SECTION 25.

DESCRIPTION: 1/2" REBAR WITH A RED PLASTIC CAP STAMPED "TOMKINS CONTROL", 100± WEST OF STATE HIGHWAY NO. 11, 850± NORTH OF THE SOUTH LINE OF SECTION 24 AND 10' SOUTH OF A FIELD ROAD.

GEODETIC COORDINATE: NAD 83(91)

LAT: 45°57'52.92054" N.

LONG: 118°23'18.04531" W.

STATE PLANE COORDINATE: NAD 83(91) OREGON NORTH ZONE (3601)

N: 257510.058 METERS

E: 2663659.608 METERS

N: 844849.272 INT. FEET

E: 8739040.720 INT. FEET

ELEVATION: 277.12 METERS

909.20 FEET

ELEVATION DATUM: NAVD 88

THETA: 1°29'51.2"

GRID FACTOR: 0.999991216

SEA LEVEL FACTOR: 0.999956512

COMBINED SCALE FACTOR: 0.999947728

CONVERSION:

METERS X 3.28083333333 = U.S. FEET

METERS X 3.28083989501 = INTERNATIONAL FEET

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Greg E. Flowers

OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/99

6/17/98