

6N57 121

TOMKINS LAND SURVEYING, INC.  
20 EAST POPLAR, SUITE 204  
WALLA WALLA WA 99362  
PHONE: 509/522-4843  
FAX 509/522-1902  
email: tomkins@wwics.com

JUNE 17, 1998

**HORIZONTAL CONTROL DATA**

STA. NAME: 905

LOCATION: TOWNSHIP 6 NORTH, RANGE 35 EAST, WILLAMETTE MERIDIAN. 1/4 CORNER  
COMMON TO SECTIONS 25 & 26.

DESCRIPTION: 3/4" IRON PIN 0.1' BELOW THE SURFACE OF THE ASPHALT AT THE INTESECTION  
OF APPLETON ROAD AND WEIS ROAD..

GEODETIC COORDINATE: NAD 83(91)

LAT: 45°58'09.20579" N.

LONG: 118°23'32.69077" W.

STATE PLANE COORDINATE: NAD 83(91) OREGON NORTH ZONE (3601)

N: 258004.460 METERS

E: 2663331.268 METERS

N: 846471.325 INT. FEET

E: 8737963.480 INT. FEET

ELEVATION: 271.42 METERS

890.48 FEET

ELEVATION DATUM: NAVD 88

THETA: 1°29'40.8"

GRID FACTOR: 0.999992320

SEA LEVEL FACTOR: 0.999957407

COMBINED SCALE FACTOR: 0.999949728

CONVERSION:

METERS X 3.2808333333 = U.S. FEET

METERS X 3.28083989501 = INTERNATIONAL FEET

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Greg E. Flowers*

OREGON  
JUNE 30, 1997  
GREG E. FLOWERS  
02820LS

RENEWS 12/31/99

6/17/98