

Report Field notes & Plat of Bounty  
 Road from S.E. cor of Sec 30. T.H. N.R.  
 33 E. to Cold Spring Landing. begun  
 Aug 30<sup>th</sup> 1880

To the Hon County Court Wm. Miller County  
 Oregon. we the undersigned. viewers appointed by  
 your Hon body to view out and survey a bounty Road  
 from S.E. cor of Sec 30 T.H. N.R. 33 E to Cold Spring Landing  
 on the Columbia River would respectfully report that  
 we met at the time and place appointed and calling  
 to our aid B.F. Raley as marker and Jas Wells & Wm Shaper  
 as chainbearers. who were each duly qualified by  
 Jno S Arnold surveyor. we proceeded to view out and  
 survey said Road. we would further report the Road  
 located on the most practical route and much needed  
 and we would recommend that the petition for said  
 road be granted

R Wells  
 Jas. Jones } viewers  
 J.R. Porter }

Field notes to Road from S.E. cor of Sec 30. T.H. N.R 33 E to  
 Cold Spring Landing begun Aug 30 1880

- Var 20° E set initial Post at S.E. cor Sec 30 T.H. N.R. 33 E
- W 40<sup>ch</sup> along line bet secs 30 & 31 to 1/4 sec cor bet same
- N 80 through center of Sec 30. set 1 m P in bottom of Jos Millers Run
- " 46.50 " " cent sec 30 to 1/4 sec cor bet secs 19 & 30 passing through lane
- W 75.46 to cor for Secs 24, 25, 19 & 30
- " 80 set 2 m P on N hill side in lane E of Mr Kendalls Run
- " 35.24 to 1/4 sec cor bet secs 24 & 25

3M

N 60° 30' W 80<sup>ch</sup> set 3 m P on N side of flat near Cargills Run

" 26<sup>ch</sup> set angle stake on N side of flat opposite Ravine on N

N 67° W 65 set a S at foot of bluff on N side of Cold Spring cañon

4M

N 65° W 80 set 4 m P in N side of flat gulch N

" 4.50 set a S in flat cabin bears S 21° E

S 86° W 57.50 down cañon set a S in flats E of Keeney & Wulevans lane

5M

N 88° W 80. set 5 m P. on S side of laid out Road near K & W Run

N 70 W 31.50 down cañon set a S opposite ravine N"

N 81° 30' W. 52 " " S side of cañon

6M

W 80 down cañon set 6 m P in flat ravine on N side of cañon