

F^Y ROAD NO
164
Change

Report of Viewers. Field Notes ^{and} Plat of Survey of a change in a County Road through the lands of Holdman Bro^r et al. Adams

Viewers Report

To the Hon County Court for Umatilla County, State of Oregon.

We the undersigned appointed by your Hon Body, to view out change in County Road No 164 in the above named County ^{and} State to-wit: Commencing at a point 580 feet North of the S. E. cor of N. W 1/4 of Sec 4 T. 3 N. R 34 E. W. M. running thence E. 250 feet, thence S. 410 feet, thence E. to Wild Horse Creek on the line of Umatilla Indian Reservation, would respectfully report that we met with Jno C. Arnold, Surveyor ^{and} select^d W^m Ruez ^{and} W^m Holdman as chain bearers ^{and} G. W. Buchanan as marker proceeded on the day set by your Hon Body to view, survey, ^{and} mark out said change in said County road, we find the change as compared with the original road between said points of beginning ^{and} ending of said proposed change, to be no longer ^{and} located on as good grounds ^{and} in every way as practicable to travel, we therefore recommend that said change be granted ^{and} that so much of the original road as is replaced by said change be vacated, ^{and} the ground thereat to revert to the proper owners or owners.

Witness our hands this 18th day of July A.D. 1884. A. M. Kenzie }
W^m H. Ferguson } Viewers
J. F. Adams }

Field Notes.

To the Hon County Court for Umatilla County, Oregon.

I herewith submit the field notes ^{and} plat of the change in County Road No 164 as surveyed by me July, 18th 1884. I met in the town of Adams in the above named County ^{and} State, W^m H. Ferguson, J. F. Adams ^{and} A. M. Kenzie, whom I qualified as viewers, W^m Holdman ^{and} W^m Ruez, whom I qualified as chain bearers ^{and} G. W. Buchanan whom I qualified as marker, on the date above given, ^{and} forthwith proceeded to execute your order to survey out change in County Road No 164 of which the following are the field notes.

I. commence 580 feet North of the center of Sec 4 T. 3 N. R 34 E. set fir post 4x4x42 inches marked R on East side in mound 4x4x1 1/2 feet, ^{and} run East 250 feet along South limit of Road to West line of Morrison Street in the town of Adams, set stake 2x2x18 inches marker AR ^{and} run South, along West limit of road 410 ft to center of Commercial Street in the town of Adams set stake 2x2x18 inches marked AR ^{and} run East along the center of road 2560 ft to center of channel of Wild Horse Creek, set fir post 4x4x42 inches on West bank of creek, post marked R on West side ^{and} a mound raised 4x4x1 1/2 feet, whole distance 3220 feet, surface sloping toward East, no rock nor trees.

Jno C. Arnold. Surveyor.