

cont to
manor 60

Report of Viewers. Field Notes and Plat of Survey of County Road from the 1/2
mile stake on E. side of Sec 22 T¹p¹N. R 26 E to intersect Co Road running from
Castle Rock to Heppner

Road No 211

Report of Viewers

Heppner Aug 18th 1884

To the Honorable County Court of Umatilla County, State of Oregon.

Greeting, We Stephen Leland, Geo Carmichael and Frank Goble having
been appointed by your Honorable body as viewers and Julius Keithly, Surveyor
to view, survey and lay out Road No 211, met at the place and time appointed and
Geo Carmichael not living in the vicinity, we Stephen Leland and Frank Goble as viewers
and Sterling Keithly, and Stephen Leland as chain bearers and being first duly sworn
proceeded to view, survey and lay out Road No 211 and find the above named road a
good and practicable route, one that is necessary to the people in the immediate
vicinity and the public generally, we therefore recommend the passage of the road.

Stephen Leland }
Frank Goble }

Field Notes

Heppner Aug 18th 1884

Road No 211.

Commencing at the 1/4 Sec corner on East side of Sec 22 Town one North
Range 26 East W. M. where I planted a post 4 inches square marked with the letter R,
thence proceeded due West 80 chains where I planted a stake 4 inches square 15 ft South
of line making one mile, thence West 80 chains where I planted a post 4 in square mar-
ked 2 miles = 30 ft South of line, thence still West 40 chains to 1/4 Sec corner on West side of Sec 20
same town and range, thence North 5 chains where I planted a post 4 inch square 30 ft East of line,
marked 3 miles, thence North 35 chains to N.E. cor of Sec 19, thence West on Sec line between Secs 18
and 19 same Town and range distance 45 chains where I planted a post 4 inch square 18 ft North
of line, marked 4 miles, thence still West, dist. 80 chains where I planted a post 4 inch square
30 ft North of 1/4 Sec, corner of Sec 24, Town one North, Range 25 East, marked V M. thence West
80 chains where I planted a post 30 ft North of line, marked VI M. still West 80
chains where I planted a post 4 inch square 27 ft North of line marked VII M. still West
80 ch to 1/4 Sec corner on North side of Sec 21 where I planted a post 30 ft North of line, 4 inch
square marked VIII. Thence West 80 chains to 1/4 Sec corner on North side of Sec 20, where
I planted a post 4 inch square 30 ft North of line marked IX M, also R, the point of termination

of Road No 211

State of Oregon }
County of Umatilla }

Hereby certify that the above plat and specifications of Road No 211 are true and correct,

Aug 20th 1884.

Julius Keithly, Deputy County Surveyor.