

Section  
Manor Co

Report of Viewers. Field Notes and Plat of Survey of a County Road from 1/2 mile stake on N line Sec 20 Tp 1 N. R 25 E. intersecting Co Road from Cluff's Lane on Willow Creek to Castle Rock Road No 227

Report of Viewers.

Aug 28<sup>th</sup> 1884

To the Honorable County Court of Umatilla County, State of Oregon,  
Greeting: We A. C. Pettys, Fred Geinger and W. L. Worthington having been appointed by your Honorable Body as viewers and Julius Keithly, Surveyor to view, survey, and lay out Road No 227, meet at the place and time appointed, and taking Stephen Heland and Frank Goble as chain bearers and Sterling Keithly as marker, and being first duly sworn proceeded to view, survey, and lay out Road No 227 as described in petition and after having viewed, surveyed and layed out said road, find the route a good and practicable one, and a road necessary to the neighbourhood and people generally.

We therefore recommend the passage of said road by your Honorable Body.

A. C. Pettys } Viewers on  
Fred Geinger } Road No 227  
W. L. Worthington }

Signed by order of the viewers, Julius Keithly.

Specifications of Road No 227. Heppner Aug 28<sup>th</sup> 1884

Commencing at the 1/4 Sec corner on the North line of Sec 20 Tp 1 N. R 25 E. W. M. where I planted a post 4 inch square marked R, 30 ft North of said corner with mound according to law, thence due West distance 80 chains where I planted a post 4 inch square marked I. M., 30 ft N. of line still due West 80 chains where I planted a post 4 inch square 30 ft N. of line marked II. M., still West 80 chains where I planted a post 4 inch square 30 ft N. of line marked III. M. thence still West to 1/4 Sec. corner on N side of Sec 23, Tp 1 N. R 24 E. W. M. distance 6 7/10 chains where I planted angle stake, thence N. 79 1/2° W. dist 66 2/10 chains, thence N. 47 1/2° W. dist 7 chains where I planted a post 4 inch square marked IV. M., thence in same course S. 47 1/2° W. dist 8 1/10 chains, thence N. 62 1/2° W. dist 16 5/10 chains, thence N. 26 1/2° W. dist 22 0/10 chains, thence N. 30 1/2° W. dist 30 0/10 chains to the S. W. corner of Sec 10 Tp 1 N. R 24 E. W. M. point of termination where I planted a post 4 in. square marked V M and R. with mound and all angle stakes set and marked according to law.

State of Oregon }  
County of Umatilla }

I hereby certify that the above Plat and specifications of Road No 227 are true and correct.

This 28<sup>th</sup> Aug 1884.

Julius Keithly  
Deputy County Surveyor.