

Field notes and Plat of Resurvey of County Road up Wild Horse Creek from crossing of same by Co Road leading South from S.E. corner Sec 30 & 4 N. R. 33 E.

## Field Notes

To the Hon County Court for Umatilla County, Oregon,

In the Matter of Resurvey of County road beginning at the point where County Road leading Southward from S.E. cor. of Sec 30 & 4 N. R. 33 E. crosses Wild Horse Creek. thence up said Creek &c

I have to report as follows.

I selected Ira Buzan to act as flagman, Lincoln Jay and Olin Ross as Chainbearers, and Lincoln Jay, marker, after qualifying each, according as required in law, I commenced at the foregoing designated point Oct 20, 1887, and run according to original field notes, and find after properly testing courses & distances, that the Courses are very incorrect and consequently the field notes of no assistance, I postpone further work until Oct 23, 1887, and engage in getting to-gether evidence concerning Courses as stated, Resuming the survey at the latter date, after dequalifying Sylvester Kelsay to act as chainbearer, or marker, as req. by law, I return to point of beginning, and set sawed fir post 4x4x42 ins. marked R. on E. side near S. bank of Wild Horse Creek. I run, thence -  $va$   $21^{\circ} E$ .

N.  $79^{\circ} E$ . 32.25 chs. found original A. S. (angle stake) set same in mound to S. of traveled road. N.  $33^{\circ} 30' E$ . 80.00 chs. set sawed fir post, as described marked I M. 38 links W. of R.C. (road center) near Res. of Townscent, 21.00 chs. set A. S. at foot of bluff, near Creek on N. - N.  $67^{\circ} 00' E$ . 35.00. set A. S. in mound at foot of bluff, 45 links S. of R.C., and drove stake at R.C. - N.  $51^{\circ} 20' E$ . 80.00 chs up Wild Horse Creek, along traveled road, set post, as above describes, marked II M. 45 lks. N. of R.C. - Beale's house N.  $38^{\circ} 45' W$ .

(At this point I run a series of random lines and locate line running N 78. through center Sec. 29 & 3 N. R. 33 E.) - N. 6.90 chs. intersect line running N 78. through center Sec. 29 & 3. N. R. 33 E. about 2 rods S.W. of bridge. at crossing of W. N. Creek. set A. S. about 25 ft. N. W. - North 7.50 chs. along said N 78. line through 29 to W. N. Creek - North 80.00 chs along said N. 78. line cross creek. along traveled road in lane ascending - set post as before describes, marked III M. 45 lks. E.

(At this point I run a series of random lines and prove the  $\frac{1}{4}$  S. cor. bet. Secs 20 & 29 to have been correctly established)

North 2.50 chs.  $\frac{1}{4}$  S. cor. bet. Secs. 20 & 29 & 3 N. R. 33 E. 80.00 chs on random N 78. line through center Sec. 20 set Temp. 4 mile post,

(At this point failing to find  $\frac{1}{4}$  S. cor. bet. Secs 20 & 17. after diligent