

the same being a contested point, I proceed to Gov. Cor. for Secs 17, 18, 19 & 20. find charred stake (in state of decay) mound, pit &c. I reset basalt stone 6x6x15 inches, 6 dim notches on E. cut with spade, thence I run East 40.20 chs. along fencing - on random - finding no corner, set temp $\frac{1}{4}$ S. cor. ^{and} continue line 80.40 chs. along traveled road in lane, failing to find cor. for Secs 16, 17, 20 & 21, I proceed to establish it as follows: after setting Temp Cor. last named, I find Gov $\frac{1}{4}$ S. cor. bet Secs 20 & 21 charred stake mound & pits; I set in place of stake, a basalt stone $6\frac{1}{2} \times 8 \times 18$ ins. marked $\frac{1}{4}$ on N. side, ^{and} run thence Va. $20^{\circ} 50' E.$ North 40.00 chs. set 2. Temp Cor. 2 lks West of 1 Temp Cor. said Secs. 16, 17, 20 & 21 - North 80.00 chs. find no corner - set Temp $\frac{1}{4}$ S. cor. bet Secs 16 & 17 ^{and} continue along trav road in lane - North 119.43 chs. find Gov. cor. for Secs 8, 9, 16 & 17 in crossing of roads N & S ^{and} E & W. Beck's School House bears S. $46^{\circ} W.$ 182 links. The charred stake being in state of decay, I set in mound a basalt stone $7 \times 12 \times 23$ ins. marked 4 notches on E. ^{and} 2 notches on N. - I also set basalt stone $7 \times 12 \times 23$ ins marked 4 notches on E. ^{and} 3 notches on S. corners, in mound in cor. of field 19 links S. of Temp. Cor. for Secs 16, 17, 20 & 21, for Perm. Cor. for said sections. I find the line from this cor. to cor for Secs 17, 18, 19 & 20 to bear S. $89^{\circ} W.$ I therefore set basalt stone $3 \times 6 \times 13$ ins. marked $\frac{1}{4}$ on N. side, one link W. of Temp. Cor. or 40.19 chs. from either N. cor. to said Sec. 20. ^{and} on line bet same for Perm $\frac{1}{4}$ S. cor. as described. While setting this corner, the original Gov. charred stake was dug up about 30 inches S. W. of pt. I established ^{and} I reset stone in exact original Gov. cor.)

I am now prepared to set Perm. 4 mile post. S.S. sawed fir, as before described, marked **IVM**. ^{and} set about 30 lks. E. of line run N & S. through center Sec. 20 or R. C. - North 2.77 chs. along said N. & S. line - $\frac{1}{4}$ S. cor. N. boundary, Sec. 20 bet A. & S. in mound about 10 ft W. of R. C. - East 42.96 chs. cor. for Secs. 16, 17, 20 & 21. S. N. R 33 E. There being no trouble about the road beyond this point, I conclude the survey.

Oct 25th 1884.

Jno C. Arnold,
Surveyor

See Page 476 for Plat of above described Road.