

Field Notes and Plat of Resurvey of County Road commencing
86 rods East of N. E. cor. of S. E. $\frac{1}{4}$ Sec. 30 T. 4 N. R 34 E.

Field Notes

To the Hon. County Court, Umatilla Co., State of Oregon.

In the matter of resurvey of County road, leading Northward
from a point 86 rods E. of N. E. cor. of S. E. $\frac{1}{4}$ of Sec. 30 T. 4 N. R 34 E. I
have the honor to report that after qualifying Wiley Frazer and W. N.
Bond as chainmen and Wiley Frazer as marker.

I commenced at $\frac{1}{4}$ Sec. cor. bet. Secs. 29 & 30 T. 4 N. R 34 E and ran
on 21° (assumed)

N $88^\circ 30' E$ 22.25 ch. along traveled road in lane, to intersect center of
traveled road in lane near residence of Wm. Hales, set split
pine post 4x5x48 in. marked R. on N. side 45 links S. of R.
C. (road center)

N $1^\circ 00' W$ 40.50 ch. set A. S. (Angle Stake) 45 links E of R. C.

S $88^\circ 00' W$ 62.76 ch. along traveled road in lane near Res. of D. A. Reeder
to cor. for Secs. 19, 20, 29 & 30 in said Sp. Cut A on N. side of old
sawed fir post 4x4 in. having A on E. side and set in ground
S. of R. C.

N $1^\circ 15' W$. 80.00 ch. along traveled road in lane; set split pine post
4x5x48 in marked 1 M on E. side 30 links W. of R. C.

do 62.66 ch along traveled road in lane, to cor. for Secs 17,
18, 19 & 20 in said Sp, set A. S. 48 links S. E of R. C against
fence cor.

N. $89^\circ 30' W$, 80.00 chs over Summit; set pine post 4x4x48 ins marked
11 M. on N. side. 30 links S. of R. C.

do	12.42 chs.	cross fence	} same fencing belonging to W. S. Claypool.
	19.70 "	" "	
	22.50 "	" "	
	23.84 "	" "	

64.47 " Cor. for Secs 18 & 19 on W. boundary of said Sp

The line bet said Secs 18 & 19 rendered somewhat inde-
fine on account of the $\frac{1}{4}$ S cor. bet. the Sec's becom-
ing extinct; I reestablished the same, as follows;

Commencing at cor. for said Secs 18 & 19 on Sp
line (being at this point) I run

S. $89^\circ 30' E$. 40.00 chs set temp $\frac{1}{4}$ S. Cor

81.80 " cor. for Secs 17, 18, 19 & 20 T. 4 N. R 34 E. (Field

Notes of original survey makes this line bet 18 &