

ROAD No

265

Road No 265

Report of Viewers, Field Notes and Plat of Survey of a County Road commencing at the Mount Pleasant School House and ending at Yoakum Station.

Report of Viewers

Yoakum Station, Aug 31st 1886

To the Hon. County Court, Umatilla County, Oregon.

We the undersigned viewers on County Road No. 265, leading from Mt. Pleasant School House to Yoakum Station, would respectfully report that we have, in connection with the County Surveyor, Jno C. Arnold, viewed out and surveyed said road as petitioned for; we find the route quite practical for a wagon road, and the road is much needed for the accommodation of the public, we therefore recommend that the petition be granted and the road established.

Most Respectfully submitted

Robert Walker

R. D. Spear

S. M. Cauley

Viewers

Field Notes of the survey of County Road No 265. -

Course Chains

I commence at center Sec. 7 T. 3 N. R 31, the S.W. cor. of School Lot, for Mt. Pleasant School - and run

South	40.00	1/4 Sec. cor. bet Secs. 7 & 18. Pendleton & Echo Road E & W.
	80.00	Set 1 mile post, 25 links west of line in Perkins field
	0.70	Center Sec 18 - wire fence E & W
	41.00	Line bet Secs 18 & 19
	80.00	Set 2 m. post 45 links west of line
	0.70	Center Sec. 19. - wire fence E & W.
	40.50	Set angle stake against angle of fence in lane N & W.
West	80.00	on line bet. Secs. 19 & 30 - along road in lane E. & W. Set basal stone 19 x 12 x 9 ins marked 3 M on S side 25 links N of line
	2.50	Cor. for Secs. 18 & 19 on line bet ranges 30 & 31 E
South		Set angle stake against angle of fence E & S.
	80.00	along range or Sp line - road in lane - Set 4 m post 20 links west of line -
	2.70	Sec. cor. for Secs 19 & 30 - Pendleton & Echo road E. & W
	71.00	Set angle stake 25 links west of line and angled toward Umatilla River - Descend around head of ravine S.
S. 50° 06' W	79.00	Set angle stake near old road Descend
S. 13° 50' E	80.00	Set 5 m. post 20 links N. of line ..