

U.
423
at
423,
W. W. River
h and
h and
ords fence
Point
dia. and
T sides
N. W.
eased
reputed
to E. against
nt of river
ee runs E & W.
lake
links North
dia. marked
e

70.10 W. W. River 20 links wide runs West.
 72.50 Set angle stake about 5 links west of fence N & S, and
 Turn 25° 10' Right around bend in river
 S 25° 10' W 74.66 Set angle stake 30 links E. of pt. on W. bank of river
 Turn thence 41° 35' Left, to intersect Sec. line
 S 16° 30' E 78.62 Int. line bet. Secs 26 & 27, 33 1/3 links South of trees & tree as above
 Turn thence along said Sec line.
 South 80.00 Set 2 mile post 30 links west of point in Mr
 Wellers field.
 Continue on reputed Sec line, road in lane.
 " 15.17 Stone Cor. 1/4 S. bet. Secs 26 & 27.
 18.04 Branch 13 links wide runs N. W.; Mr W^m Broom on
 E. side of lane
 26.75 E. B. Briggs on west side of lane.
 33.10 Branch 30 links wide runs N. W.
 39.70 " 10 " " " "
 40.20 C. Rodgers on west of lane
 49.50 F. Dullwans, " East " "
 58.41 Irrigating ditch runs across road west.
 58.54 Cor. for Secs. 26, 27, 34 & 35
 57.20 Irrigating ditch runs N. W.
 63.17 " " 3 lks. wide runs N. W.
 74.72 " " 4 " " " "
 W^m Forsythes on W. of lane.
 80.00 Set 3 mile post against fence 30 links W. of pt
 Continue on line bet. Secs. 34 & 35
 14.25 Geo. Lydell's east of lane
 14.41 Branch 6 links wide runs N. W.
 47.30 " 30 " " " west
 54.71 Cor. for Secs 2, 3, 34 & 35, on Sp line. Leave lane
 66.35 Branch 10 links wide runs west
 69.94 " 5 " " " N. W.
 71.23 " 4 " " " "
 73.30 " 4 " " " "
 77.10 " 3 " " " west.
 77.16 Set angle stake at point, 50 ft N. of R. R. track
 Turn thence along line, parallel to R. R. track,
 and 50 ft from center of same.
 S 67° 15' E 80.00 Set 4 mile post 45 links N. of point.
 41.00 Intersect line N & S, Center Sec 2, 35 N. R 35 E.
 The western bndy. of North Millon; Set post
 for terminus 45 links N. of point in field.

I hereby certify that the foregoing are the true field notes of the survey of Ross 1850 2 for Yamhill Co. Oregon
Jno E Arnold
County Surveyor