

of decomposition, 12 ins. below surface; I. therefore, move temp. to S. cor. 9 lks. west<sup>and</sup> 26½ lks. South<sup>and</sup> set a porous basalt boulder 21x14x6 ins., marked with a cross on top end set a few inches below surface, in south track of traveled road, at west end of lane, course East.

Point, purporting to be locality of Gov. ¼ S. cor. bet. Sees. 17420. I verify by O. W. McDonald<sup>and</sup> Wm A. Wells<sup>and</sup> set over old decayed stake, a basalt stone 20x15x10 ins., marked ¼ on N. face; A wire fence, 45 links N. of this cor., runs E & W.

I run thence on random line bet Sees 17421 Var. 18° 45' E 20.00chs, set temp to S. cor. on hill side facing N. W. 39.88chs Int. N & S, line 41 links N. of Sec. Cor. for Sees 17. 18. 19 & 20; Gov. stake found lying on plain mound with 4 distinct pits (N. S. E & W) old furrows cross this cor. N & S<sup>and</sup> E & W<sup>and</sup> 30 lks west, a wire fence runs N & S. To preserve this cor., I set a porous basalt stone 14x8x6 ins., with 5 notches on E. Cor.<sup>and</sup> 3 notches on S cor. 12 ins. in ground.

I. therefore, move temp to S. cor. on W. ½ of line bet. Sees. 17420, South 20½ links<sup>and</sup> 12 links west<sup>and</sup> set a smooth boulder, marked with a cross on top. 18 ins. below surface; dug pits N. S. E & W<sup>and</sup> raised mound above corner.

I measure from 24<sup>th</sup> mile post on the line bet. Wash. Terr. and State of Oregon, var. 18° 45' E. 13.65chs West on random State line, to ascertain locality of cor. for Sees. 17418 in said T<sup>err</sup>. Set temp cor. for said Sees. 17418

I run thence East on random State line 13.65chs, 24<sup>th</sup> mile post

Monday, March 26<sup>th</sup> 1888

20.00chs set temp to S. cor. 40.00chs set temp ¼ S. Cor. 60.00chs set temp to S. Cor. 80.64chs Int. N & S, line, a few feet N. of Cor. for Sees. 16 & 17, claimed by Wm Kralman & Son Joseph Kralman - both present to have been standing<sup>and</sup> unquestioned some five years ago, when they built certain ditch fences, beginning 15 ft. measure south of said cor.<sup>and</sup> running on random lines S.<sup>and</sup> E.

I find 25<sup>th</sup> mile post<sup>and</sup> measure west var. 18° 45' E. 13.50chs, a pt. N. of W. side of ditch fence N. & S.<sup>and</sup> center of ditch fence E & W.<sup>and</sup> 15 ft. S. of pt. claimed by said Kralman & Son as original cor. for said Sees. 16 & 17. I find point about 5chs. W. from this cor. whence I can see poles set in ground at 24<sup>th</sup><sup>and</sup> 25<sup>th</sup> mile posts.<sup>and</sup> thus establish true State line between same by moving temp ¼ S. cor 32 links East<sup>and</sup> on true line, set a round basalt stone 14 ins. long & 8 ins. dia., marked ¼ on S. side. At this point there are indications of old mounds & pits.

From this cor. Richard Salbert's house bears N. 82° E about 150chs,