

ROAD NO
320.

- Road No. 320 -

Report of Viewers, field notes & Plot of Survey of a County Road Com', at the quarter stake or as near as practicable between sec's 23 & 26 Tp 5 N. R. 34 E. Running Westerly on Sec line to N.W. Co. of Sec. 28 N.E. Co. Sec. 29 S.E. Co. Sec. 20 & S.W. Co. Sec. 21 Same Tp. & Range

- Report of Viewers. -

To the Hon. County Court
Umatilla County, Oregon:-

We the undersigned, your viewers on Road Survey No. 320. would respectfully report that we met County Surveyor Jno. C. Arnold at the time & place set for the same, & calling to our assistance A. M^c Donald, & L. B. Jay and Elton Waterman, after being qualified, each, according to law, we proceeded to view out & survey said road as prayed for in petition for the same.

We find the road located upon comparatively good ground, & one that is very much needed by the community as an easy outlet to the O. & W. T. R. R.

The road, in general, is located upon section lines.

We therefore recommend that said road 320 become a public highway.

David Taylor

F. M. Mansfield

E. A. Dudley

Field Notes of Road Survey No. 320 for Umatilla County, Or.

I met viewers, David Taylor, Frank M. Mansfield & E. A. Dudley, as per order of County Court, March 23^d 1889, & administered the usual viewers oath to each. I called Elton Waterman & L. B. Jay to act as chainmen, & L. B. Jay to mark. As the proposed road runs through a number of fields, fenced with wire, I found it necessary, also, to call A. M^c Donald to drive team & assist in getting stakes spades &c. to proper points. Each assistant was qualified by taking the usual form of oath.

I set initial post 300 links East of $\frac{1}{4}$ S. Co. bet. Secs. 23 & 26 T. 5 N. R. 34 E. on N.W. hill side, from which a school house bears ^{South} East 48 yards distant. Weather windy & cloudy. Var. 20° 30' E. I turn left 40°, around head of hollow.

3.00 Set angle stake at point, & cut A on post in fence S.W. 6 lks.

Turn, thence, Right 85° ascending gently to Sec. line.

7.20 Draw stake on line bet. Secs 23 & 26 at Station point, & cut A on post in fence on N side of lane, 29 links N. of Pt. Turn, thence, West on Sec. lines.

9.00 Summit; Descend gently.

17.00 Ravine - 10 runs South. Ascend.

30.00 Summit. Descend gently.

45.30 Ravine.

67.50 O. & W. T. R. R. track, N. 16° 30' W. & S. 16° 30' E. < Approximately >

Ascend.