

Field Notes of Road Survey no 338 for Multnomah County Oregon.

I met full board of viewers on R 338 at time and place appointed for the same, and administer to each the usual form of oath. We call Edgar Thomson and D.E. Clark to chain and mark and L.M.M. Reynolds as assessor and qualify each according to law. I commence at a pt on R 241 on foot of steep grade on E side of Lewis Creek in SW 1/4 of D & 1/2 of Dec 4 & 5 O.R. 32 & and on var 200' - initial post 45' South of foot of grade and 110' E of Lewis Creek. I run from said initial post.

S 46° 18' W	315	Center of Lewis Creek course S 57° W 50' wide
	389	Set angle post - cut A on alder in bunch on S side of Creek and turn
S 18° 31' E	562	Set angle post, and turn.
N 76° 14' E	584	Foot of grade ascend,
	650	Head " " less ascent.
	841	Set angle post and turn,
S 86° 46' E	1678	But A on S side of Pine stump 14" high 2" dia and turn
S 45° 26' E	2046	Pine tree 20" dia on line, notched 3 notches in line
	2370	Set angle post about 25' E of Pine grove, and turn.
S 42° 35' E	3000	Summit
	3758	Large pine, 18" dia, notched on opposite sides 3 notches but A on West side
	4122	Intersect line bet Dees 9 & 10 set angle post in mound with pits and turn.
South	5120	1/4 Dec Cor bet Dees 9 & 10 continue on Dec line
	5280	Set 1 M.P. 20' E. of line " " " "
	7440	Cor for Dees 9 & 10 - 15 & 16 " " " "
	8133	" " 1/4 Dec bet Dees 15 & 16 " " " "
	8280	Set 2 M.P. 20' E of line but A on mile post & turn
S 43° 36' E	1266	" Angle post in mound and turn
	7869	Cor fences S & W. on West side of E end of lane 20' wide course N & S. cut A on cor post and turn
South	7660	Rainie 25' wide runs NW rocky.
	8385	Cut 11 M on on a porous basalt rock in place 48 x 30 x 20 ins.
	95	S end of lane cut A on cor post fences N & W. on west side of lane and turn.
S 50° 20' W	7444	Set angle post in traveled road and turn.
S 76° 12' W	1195	" " " " " "
S 87° 27' W	1561	" " " " " "
N 76° 53' W	1924	" " " " " "