

carriers oaths, also C. B. Davidson called, and administered usual oath for marker

I commence at $\frac{1}{4}$ Sec cor bet Secs 26 & 27 in $\frac{1}{4}$ sp
 & C.R. 36 & setting the initial post S $52^{\circ} 15'$ E 25
 feet distant from said cor. var 20° E

I run west on true line E. & W. through the center
 of said Sec 27 descend. - scattering trees & shrubs
 1367 ft to $\frac{1}{4}$ Sec cor

1490 Gulch runs NW; ascend

1700 ft Set angle post on E. hill side, at point on
 center line of road: a fence marks the road
 to this point. I turn thence right $25^{\circ} 50'$

2035 ft. Cut A on South side of burnt pine tree 24"
 dia, on rock point, and turn thence Left $66^{\circ} 10'$

2450 ft. Cut A on west side of red fir 16" dia in ravine
 course about C. 15° W and turn thence Right $74^{\circ} 45'$

2506 ft. Cut A on small fir 2" dia and turn thence Right $54^{\circ} 15'$

2738 ft. Out line E. & W. through said Sec 27, leaving fence
 E. & W. I turn thence along said $\frac{1}{2}$ Sec line west

3064 Old Cor Center said Sec 27

3165 Old well in Ravine C. E.: ascend

3438 I intersect traveled road C. W. & SE

I set angle post on center line of road and 10 ft East
 of Station and turn from Station R $51^{\circ} 30'$

4039 ft. Set angle post on point of Road line, among small
 pine trees and turn thence left $21^{\circ} 30'$

4400 ft. Set angle post at point on road center on North
 side of traveled road and turn thence Right $30^{\circ} 45'$

5230 ft. Set 1 mile post 15 ft South of center line of road
 and continue course

525 ft. to pt 4 ft C. of N.E. cor of school house grounds as
 shown by fence. I set R on E side of Pine tree 8 in
 dia, and 6 ft South of pt for terminus of road 329

Whereby certify that the foregoing notes of the
 survey of County road 329 for Multnomah County
 Oregon are correct

Jno C Arnold
 Surveyor

Filed Nov 2-1889
 G. L. Hartman Clerk

I
 Survey
 Meridia

Filed
 G. L. Hartman
 Clerk