

run thence,
 S 2° 37' W, 263 ft. First angle post on 9 mile P. & D. road; Turn
 South 87° 5". A discussion as to proper course arises &
 other rivers are sent for.

Tuesday May 10.

Madison Jones a second river appears upon the
 scene, is duly qualified according to law, and after
 some lengthy considerations I am ordered to resurvey
 from commencement and change course. I accord-
 ingly cut R on the south side of the 8 mile post
 above described and having secured the assistance
 of P. R. McDonald whom I qualified to act as chum.
 I run from said 8 mile post, descending;

	feet	
S 27° 00' W.	1330	Intersect line bet. Secs 26 & 27 S 1/4 N. 32 E 44° S south of corner for Secs. 22-23, 26 & 27 said Tp. set angle stake at point and turn on sec line.
South	1930	Ravine - 40', course W; ascend.
	2700	Summit; descend
	2950	Flat
	3530	Enter field Stone cor under center of leaning fence E & W.
	4783	Leave field
	5050	Descend gently
	5280	Set 1 mile post 25' east of line in plowed ground near Bealohouse. Continue course on sec. line bet Secs 26 & 27.
	783	Cor. for Secs. 26, 27, 34 & 35.
	2560	Ravine Course NW. ascend gently.
	3440	Summit.
	3900	Descend gently
	4950	Foot of descent, in flat east of ravine, course N.
	5280	Set 2 mile post 25' east of point. Continue course on sec line bet. Secs 34 & 35 S 1/4 N. 32 E.
South	809	Cor for Secs 2, 3-34 & 35 on Tp. line bet Tps. 2 South set angle stake at said cor. and turn.
West	859	Ravine course, N - ascend. enter lane along traveled road.
	1359	Summit - 20'
	2000	Enter point of angle of road in lane E & S set angle stake 27' west of point at fence on W side lane, turn on sec. line bet Secs. 2 & 3 S 1/4 N. 32 E along road in lane.
South	5240	Set 3 mile post 25 ft east of line, at fence east side lane.