

This is to certify that I met the within named miners on the day and place appointed and was duly sworn as a viewer on the within described road.
 Filed Sept. 8 1891
 W. M. Birce Clerk.
 S. Rothchild.

Field Notes of Road Survey No 371 for, Umatilla County, Oregon

Wednesday Aug. 26th 1891, I met J. M. Watson and R. Y. Thompson, who had by the Co. Clerk been sworn in as viewers on Road Survey 371.

We called Dude Frazer, Wm Turvell and Doaac W Kimball to chain and mark, and administered oath to each.

I set initial post on R 371, 30 East of the intersection of the base line with the line bet. Ranges 32 + 33 E and with Engineers Transit I run from said point of intersection, along said Range line

North	2650	Set Dec. Cor. bet Decs 31 + 36
	5250	Set 1 m. p. 30 E. Route good.
	100	Cor. for Decs 25-36-30-31
	450	Set angle post 1 and turn thence
N. 75° 56' E	700	Descend to creek, course N 45° E, some water. Fair grade to creek
	1110	Set a. p. 2; thence gradual ascent. Loose rock. Needs grading.
N. 58° 51' W.	1870	Intersect line bet. Decs 25 + 30. Set as 3, thence on Range line.
North	5280	Set 2 m. p. 30 E. Land level; fenced on W.
	1400	Dec. Cor. for Decs 19-24-25 + 30.
	2300	Set a. p. 4 Leave Range Line and turn, thence.
N. 80° 40' E	2673	" " 5
N. 60° 37' W.	3072	Intersect line bet. Ranges 32 + 33 E, Road steep. Loose rock. Needs grading. Set a. p. 6, and turn, thence.
North	4040	Set Dec. Cor. bet. Decs 19 + 24.
	5280	Set 3 m. p. 30 E.
	1500	Cor. for Decs 13-18-19-22
	3240	Ravine runs west. Ascent steep.
	3600	Summit. Level.
	4150	Set Dec. Cor. bet. Decs 13 + 18.
	5075	Foot of gradual ascent. Loose rock.
	5280	Set 4 m. p. 30 E. + 250 to summit, level
	1516	Cor for Decs 7-12-13-18
	4182	Set Dec. Cor. bet. Decs 7 + 12.
	5280	Set 5 m. p. 30 E. Ground level.

7128-00
 N 36°-11
 Nor
 West
 7151-15
 S 38°-36
 West
 North
 West.
 7121-00
 I
 all the
 mon
 2
 notes
 Filed
 W. M.