

Field Notes of Road Survey, No 373, for Umatilla Co. Oregon.

I meet J. E. McQuary and Jackson Nelson, viewers on road 373, at Athena, Aug. 10 1891, and administer to each, the usual form of road viewers oath. We call Edgar Thomson and Henry Zahner to assist in chaining and marking, and administer oath to each, I set initial post 30 feet east of Cor. for Secs. 19-24-25+30 on line bet. ranges 34+35 East in Tp. 4 N. and with a common open sight field compass, I run from sec. Cor. (Var. 21° E) South on range line; ascend gently

- 1700 Summit.
 2648 1/4 Sec. Cor. bet. Secs. 25+30.
 3625 Small ravine, runs NW.
 5280 Set 1 m. p. 30 feet to the East.
 continue south on range line.
 18 Cor. for Secs. 1-6-31+36
 2673 1/4 Sec. Cor. bet. Secs. 1+6
 3160 Center of lane. Course E+W.
 5250 " " " " " "
 5280 Set 2 m. p. 30 East and continue course.
 34 Cor. for Secs. 1-6-31-36 Tp. Cor. bet. Tps. 3+4 N. Rgs. 34+35 E
 800 Small ravine; course SE. ascend.
 2160 Summit; descend.
 2675 1/4 Sec. Cor. bet. Secs. 1+6
 5280 Set 3 m. p. 30 East. continue course.
 40 Cor. for Secs. 1-6-7+12.
 1100 Foot of hill.
 1440 Center of Spring hollow 30 wide.
 1550 Ascend hill.
 2000 Summit.
 2670 1/4 Sec. Cor. bet. Secs. 7+12
 5280 Set 4 m. p. 30 East. Continue course.
 66 Cor. for Secs. 7-12-13-18
 2724 1/4 Sec. Cor. bet. Secs. 13+18
 3950 Center of dry channel of creek.
 5280 Set 5 m. p. 30 East. continue course.
 93 Cor. for Secs. 13-18-19+24.
 2700 1/4 Sec. Cor. bet. Secs. 19+24.
 5280 Set 6 m. p. 30 East. continue course.
 110 Cor. for Secs. 19-24-25+30
 120 Center of lane. Course E+W. ascend.
 2766 1/4 Cor. bet. Secs. 25+30.