

We would therefore recommend that the prayer of the petitioners for road No 376, for Umatilla County, Oregon be granted.

Witness our respective hands at Pilot Rock this 9th day of Oct. A.D. 1891

A. S. Witten
 G. P. Skelton } Viewers Road Survey No. 376.
 W. Stewart }

Filed Nov. 2 1891

W. M. Pierce Clerk

By J. C. Beam Deputy

Survey of Road No. 376 for Umatilla County, Oregon.

I meet A. S. Witten, W. Stewart and G. P. Skelton at Pilot Rock, U. Co Oreg. Oct 5th 1891 each made oath to faithfully and impartially discharge the duties of his appointment of Road viewer on Road No. 376 for U. Co, State of Oregon. We called to our aid E. W. Matthews and J. C. Hill to chain and J. C. Hill to mark, who were each duly sworn.

I set initial post in mound of earth 20 ft south of a basalt stone 22x12x8 ins. set in NW¹/₄ of NE¹/₄ of Sec 20, T. 15 R. 32 E for commencing of R. 376.

		Run from said stone down cañon ^{ed} along graded road
N 35°-15' W	15.37	Set a. p. 1 and turn L 9°-42'
N 44°-57' W	17.75	Recommend culvert 4 ft.
	28.80	Set a. p. 2 and turn L 9°
N 53°-57' W	34.00	" " " 3 " " L 38°-45'
S 87°-15' W	42.00	Recommended a 12 ft. bridge
	56.00	" " " 4 " " L 24°-50'. NE Cor Sec 19 bears N 21°-32' W 450 lbs dist.
S 62°-25' W	62.30	" " " 5 " " R 12°-41'
S 78°-09' W	71.93	" " " 6 " " R 3°-40'
S 78°-49' W	80.00	" 1 m. p. Mk. of line, on south side of bridge in mound of stone.
	5.00	" a. p. 7 and turn L 24°-18'
S 54°-31' W	10.20	" " " 8 " " R 11°-28'
S 65°-59' W	16.56	" " " 9 " " R 6°-15'
S 72°-55' W	22.05	" " " 10 " " R 16°-40'
S 89°-35' W	36.70	" " " 11 " " L 18°-30'
S 71°-05' W	38.80	" " " 12 " " R 16°-25'
S 87°-30' W	43.20	" " " 13 " " L 10°-22'
S 77°-08' W	59.25	" " " 14 " " L 15°-28'
S 61°-40' W	64.50	" " " 15 " " R 11°-33'
S 73°-13' W	66.75	" " " 16 " " R 20°-26'
N 86°-21' W	76.00	" " " 17 " " L 11°-33'