

ray or of the
ounty, Oregon
y of Oct. 20, 1891

Oregon,
kelton at
to faith-
pointment
regon,
to chain
n,
with of a
J/SK32E

ed road

idge
50 kts dist,

l of stone,

S 82°-06 W	80.00	Set 2 mp. 45 kts south of line in stone mound 1 1/2 ft h x 4 ft b.
	9.75	" a. p 18 and turn R 8°-10'
S 73°-56 W	19.40	" " " 19 " " R 6°-45'
S 82°-41 W	22.50	" " " 20 " " L 1/4°-15', house bears south 150 kts. dist.
S 67°-49 W	28.25	" " " 21 " " L 1/2°-22'
S 55°-27 W	30.94	" " " 22 " " R 19°-23'
S 74°-50 W	38.00	From Lubus house bears south 350 kts. dist.
	40.00	Line bet. Ranges 32 + 33 E
	44.60	Set a. p 23 and turn R 4°-15'
S 79°-05 W	50.10	" " " 24 " " L 5°-44'
S 73°-21 W	57.55	" " " 25 " " R 16°-07'
S 89°-28 W	65.20	Set a. p. 26 and turn R. 10°-30' Tuesday, Oct. 6 1891,
N 80°-02 W	68.25	" " " 27 " " L 24°-30'
S 75-28 W	76.52	" " " 28 " " R 19°-47'
N 84°-45 W	80.00	" 3 m. p. 45 kts south of line.
	7.40	" a. p. 29 and turn L 5°-34'
S 89°-41 W	8.80	" " " 30 " " R 18°-53'
N 71°-26 W	13.00	" " " 31 " " L 3°-45'
N 75°-11 W	20.05	" " " 32 " " R 1°-10'
N 74°-01 W	25.10	" " " 33 " " L 4°-24'
N 78°-25 W	34.00	" " " 34 " " R 24°-22'
N 54°-03 W	42.90	" " " 35 " " R 29° 21' { E. Cor. bet. Secs 23 + 24 J/SR 32 E 500 kts south of a post
N 26°-42 W	45.30	" " " 36 " " L 2° 20'
N 49°-02 W	55.90	" " " 37 " " R 6°-45'
N 42°-17 W	65.67	" " " 38 " " R 10°-40'
N 31°-37 W	80.00	" 4 m. p. 45 kts south of line in stone mound,
	4.32	" a. p. 39 and turn L 15°-10'. Int. line bet. secs 14 + 23
West	8.00	On sec. line, Recommended bridge across Stewart creek 20 ft.
	61.20	Int. R. No. 229 at SE Cor. Sec 15 J/SR 32 E
		Set terminus.

(Note) Road 376 is to be located as near the hill north of Stewart creek as is practicable.

I hereby certify that the foregoing notes of Road Survey No. 376 for Umatilla County, Oregon are correct,
Jno. C. Arnold Co Surveyor.
per G. E. Waggoner Deputy.

Filed Nov. 2nd 1891
W. M. Pierce Clerk
By G. E. Beam Deputy