

## Field Notes Road No 387.

To the Hon County Court Linn County, State of Oregon  
I herewith submit Field Notes and Plat of Road Survey  
No 387

Quint George Schauer, Henry Brazier and  
Ransom Wells viewers, at Milton, Oregon, on Wednesday  
April 20<sup>th</sup> 1892, and administer to each the usual road  
viewers oath

We call to our aid J. C. Hoie J. L. Hodgen and W. L. Hodgen  
as assistants and I administer oath to each as required  
by law. I commence 10-24 chs East of the  $\frac{1}{4}$  sec cor on the  
West boundary of the SW  $\frac{1}{4}$  of Sec 29 in Tp 6 NR 35 E 10W.

Set oared fir post 4 x 4 ins - 4 ft long 24 ins in ground for in-  
itial post to Road No 387 marked R 5 on South face and  
387 on North face and raised a mound of earth  $\frac{1}{2}$  ft base  
and 2 ft high around post, against fence on North side  
of lane course E. & W.

Then Comm

Var 210.00' E

Chs S 89.00' W along center of Road in lane

87.5 Irrigating ditch 4 lks wide runs west

1000 W. L. Hodgen's house bears west about 250 lks

16.75 Spring creek swamp - water 50 lks wide runs N. W.

19.80 Culvert line bet sees 29 & 32 set angle post and turn  
west along section line

27.95 The cor to sees 29-30-31-32

set angle post No 2 and turn

South along bet sees 31 & 32 ascend

3200 Summit

61.50 Descend

64.50 Ravine Course N. W.

67.24 The  $\frac{1}{4}$  sec cor bet sees 31 & 32 Out around bearing N. E. & S. E.

Set a oared post 4 x 4 ins - 4 ft long - 24 ins in ground for  
terminus marked R on N face and 387 on S face, raised  
a mound of earth  $\frac{1}{2}$  ft base and 2 ft high around the  
post which is set 45 lks S of said  $\frac{1}{4}$  sec cor against a  
fence bearing E. & W.

I hereby certify that the foregoing are the correct field notes  
of Road Survey No 387 for Linn County Oregon

Jno C. Arnold  
County Surveyor

Filed April 26<sup>th</sup> 1892 }  
Wm. Durie Clerk }